

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LIGHTING-	SURVEIL-	SIGNING	ROADWAY	LIGHTING	SURVEIL-	SIGNING	VILLAGE			
				ILLINOIS	ILLINOIS	LANCE ILLINOIS	ILLINOIS	INDIANA	INDIANA	LANCE INDIANA	INDIANA	OF LANSING			
				CONSTRUCTION TYPE CODE											
				J000-2A	Y030-1E	Y032-1F	Y002-1C	J000-2A	Y030-1E	Y032-1F	Y002-1C	Y000			
MX030144	CATCH BASINS, 1.2M BY 0.9M SPECIAL, TYPE 20 FRAME AND GRATE	EACH	45	45	0	0	0	0	0	0	0	0			
MX030170	CATCH BASINS, 1.2M BY 1.5M SPECIAL, TYPE 22 FRAME AND GRATE	EACH	6	6	0	0	0	0	0	0	0	0			
MX030236	REMOVE STEEL SHEET PILING	SQ M	2161	2161	0	0	0	0	0	0	0	0			
MX030504	TEMPORARY PAVEMENT (INTERSTATE)	SQ M	6264	3204	0	0	0	3060	0	0	0	0			
MX030505	STORM SEWERS TO BE GROUTED	CU M	1296.1	1296.1	0	0	0	0	0	0	0	0			
* MX032159	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA. PVC, 1 WIDE X 1 HIGH	METER	329	0	168	161	0	0	0	0	0	0			
* MX032160	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA. PVC, 2 WIDE X 1 HIGH	METER	118	0	0	118	0	0	0	0	0	0			
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	91	15	0	0	0	76	0	0	0	0			
MX033183	SOIL STABILIZERS	KG	580885	115748	0	0	0	465137	0	0	0	0			
MX033290	SEDIMENT CONTROL, SILT FENCE	METER	2669.7	190.4	0	0	0	2479.3	0	0	0	0			
MX033291	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	METER	1334.9	95.2	0	0	0	1239.7	0	0	0	0			
MX033292	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ M	322	0	0	0	0	322	0	0	0	0			
MX033303	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ M	812	78	0	0	0	734	0	0	0	0			
* MX033401	CONDUIT IN TRENCH, 50MM DIA., RIGID GALVANIZED STEEL	METER	10	0	0	10	0	0	0	0	0	0			
* MX033487	BLIND FLANGE CAP, 150MM DIA.	EACH	1	0	0	0	0	0	0	0	0	0	1		
MX355200	BITUMINOUS BASE COURSE SUPERPAVE, 200MM	SQ M	90	90	0	0	0	0	0	0	0	0			
MX406012	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	M TON	32.1	11.1	0	0	0	0	0	0	0	0	21		
MX406078	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N105	M TON	52.2	52.2	0	0	0	0	0	0	0	0			
MX406220	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	M TON	36.1	36.1	0	0	0	0	0	0	0	0			
MX406271	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50 150MM	SQ M	225	0	0	0	0	0	0	0	0	0	225		
MX550175	DUCTILE IRON PIPE, STORM SEWER, 150MM	METER	28	28	0	0	0	0	0	0	0	0			
MX637150	CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT, SPECIAL	METER	113	113	0	0	0	0	0	0	0	0			
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	3881	1433	0	0	0	2448	0	0	0	0			
MX013825	CONTROLLED LOW STRENGTH MATERIAL	CU M	25	0	0	0	0	0	0	0	0	0	25		
MZ022800	FENCE REMOVAL	METER	2346	327	0	0	0	2019	0	0	0	0			
MZ068400	STEEL CASINGS 1050MM	METER	5	0	0	0	0	0	0	0	0	0	5		
X0301229	ACCIDENT INVESTIGATION SITE	CAL MO	4	4	0	0	0	0	0	0	0	0			
X0320333	ROADWAY CLEANING (SPECIAL)	EACH	18	6	0	0	0	12	0	0	0	0			
X0322394	CONCRETE FILLED STEEL POST REMOVAL	EACH	10	10	0	0	0	0	0	0	0	0			
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	10	5	0	0	0	5	0	0	0	0			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	1316	595	0	0	0	721	0	0	0	0			
X0323817	SEDIMENT CONTROL, SILT CURTAIN	EACH	3	0	0	0	0	3	0	0	0	0			
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	6	1	0	0	0	5	0	0	0	0			

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE: _____ DATE: 07/05

DRAWN BY ACE/CAD
CHECKED BY TAE

AMERICAN
CONSULTING ENGINEERS