

SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING-	SURVEIL-	SIGNING	ROADWAY	LIGHTING	SURVEIL-	SIGNING	VILLAGE			
				ILLINOIS	ILLINOIS	LANCE ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS	ILLINOIS
				CONSTRUCTION TYPE CODE											
				J000-2A	Y030-1E	Y032-1F	Y002-1C	J000-2A	Y030-1E	Y032-1F	Y002-1C	Y060			
* MX033677	FENCE GATE, CHAIN LINK, 1220 MM X 3.7 M (INDIANA)	EACH	2	0	0	0	0	2	0	0	0	0			
MX033679	SIDEWALK, CONCRETE 100 MM (INDIANA)	SQ M	277	0	0	0	0	277	0	0	0	0			
MX033680	SIDEWALK, CONCRETE 150 MM (INDIANA)	SQ M	24	0	0	0	0	24	0	0	0	0			
MX033681	CURB AND GUTTER, C, CONCRETE, SPECIAL (INDIANA)	METER	340	0	0	0	0	340	0	0	0	0			
MX033689	REINFORCED CONCRETE BRIDGE APPROACH, 400MM (INDIANA)	SQ M	3436	0	0	0	0	3436	0	0	0	0			
MX033650	MONUMENT, D (INDIANA)	EACH	3	0	0	0	0	3	0	0	0	0			
MX033681	RIPRAP, UNIFORM (INDIANA)	SQ M	44	0	0	0	0	44	0	0	0	0			
MX033651	GEOTEXTILES (INDIANA)	SQ M	44	0	0	0	0	44	0	0	0	0			
MX033652	HANDRAIL, STEEL (INDIANA)	METER	11	0	0	0	0	11	0	0	0	0			
MX033687	PIPE, TYPE 2, DEFORMED, MIN. AREA 1.68 M2 (INDIANA)	METER	12	0	0	0	0	12	0	0	0	0			
MX033653	PIPE TYPE 2, CIRCULAR, 300 MM (INDIANA)	METER	917.8	0	0	0	0	917.8	0	0	0	0			
MX033654	PIPE TYPE 2, CIRCULAR, 375 MM (INDIANA)	METER	244.1	0	0	0	0	244.1	0	0	0	0			
MX033655	PIPE TYPE 2, CIRCULAR, 450 MM (INDIANA)	METER	334.5	0	0	0	0	334.5	0	0	0	0			
MX033656	PIPE TYPE 2, CIRCULAR, 600 MM (INDIANA)	METER	693.6	0	0	0	0	693.6	0	0	0	0			
MX033657	PIPE TYPE 2, CIRCULAR, 750 MM (INDIANA)	METER	166.3	0	0	0	0	166.3	0	0	0	0			
MX033658	PIPE TYPE 2, CIRCULAR, 900 MM (INDIANA)	METER	146	0	0	0	0	146	0	0	0	0			
MX033659	PIPE TYPE 4, CIRCULAR, 150 MM (INDIANA)	METER	3225.4	0	0	0	0	3225.4	0	0	0	0			
MX033660	PIPE END SECTION, 600 MM (INDIANA)	EACH	2	0	0	0	0	2	0	0	0	0			
MX033688	PIPE, SLOTTED DRAIN, 300 MM (INDIANA)	METER	575.7	0	0	0	0	575.7	0	0	0	0			
MX033604	PIPE INSTALLATION, TRENCHLESS, 600 MM (INDIANA)	METER	59	0	0	0	0	59	0	0	0	0			
MX033603	GEOTEXTILES FOR UNDERDRAIN (INDIANA)	SQ M	7753	0	0	0	0	7753	0	0	0	0			
MX033605	AGGREGATE FOR UNDERDRAINS (INDIANA)	CU M	1023	0	0	0	0	1023	0	0	0	0			
* MX033606	VIDEO INSPECTION FOR UNDERDRAINS (INDIANA)	METER	3230	0	0	0	0	3230	0	0	0	0			
MX033607	INLET TYPE HA (INDIANA)	EACH	1	0	0	0	0	1	0	0	0	0			
MX033608	MANHOLE, C4 (INDIANA)	EACH	3	0	0	0	0	3	0	0	0	0			
MX033609	MANHOLE, D4 (INDIANA)	EACH	2	0	0	0	0	2	0	0	0	0			
MX033610	DROP MANHOLE, C2 (INDIANA)	EACH	2	0	0	0	0	2	0	0	0	0			
MX033611	DROP MANHOLE, C4 (INDIANA)	EACH	1	0	0	0	0	1	0	0	0	0			
MX033612	INLET TYPE H, (SPECIAL) WITH SLOTTED DRAIN (INDIANA)	EACH	2	0	0	0	0	2	0	0	0	0			
MX033613	INLET TYPE H, (SPECIAL) (INDIANA)	EACH	14	0	0	0	0	14	0	0	0	0			
MX033614	INLET TYPE HA, (MODIFIED) (INDIANA)	EACH	34	0	0	0	0	34	0	0	0	0			
MX033615	INLET TYPE HA, (SPECIAL) (INDIANA)	EACH	7	0	0	0	0	7	0	0	0	0			

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE: _____ DRAWN BY: ACE/CAD
DATE: 07/05 CHECKED BY: TAE

