



**NOTES**

1. Transverse joints shall be constructed perpendicular to the centerline with a maximum spacing of 5500 unless otherwise specified.
2. The configuration of the preformed elastomeric joint seal shall be a 14 to 16 wide seal with at least a five coil internal design. The seal height shall be 14 to 21 in uncompressed stage.
3. For transverse construction joints, the initial saw cut may be eliminated.

All Dimension are in mm unless otherwise specified

INDIANA DEPARTMENT OF TRANSPORTATION

**TRANSVERSE JOINT SEALS**

MARCH 2005

STANDARD DRAWING NO. 503-CCPJ-08

|  |                           |         |
|--|---------------------------|---------|
|  | /s/ Richard L. VonCleave  | 3-07-05 |
|  | DESIGN STANDARDS ENGINEER | DATE    |
|  | /s/ Richard K. Smutzer    | 3-07-05 |
|  | CHIEF HIGHWAY ENGINEER    | DATE    |