ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	362
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 62114 INDOT DES. NO. 0100987

SIGNING SCHEDULE - GROUND MOUNTED SIGNS

								ILLINOIS SIGN PANELS		STEEL SIGN SUPPORT			WOOD SIGN SUPPORT				INDIANA SIGN PANELS			INDIANA STEEL SIGN SUPPORT						
SIGN NO.	STATION	LT/RT	"AA" (M)	"BB" (M)	WIDTH (M)	DEPTH (M)	EXIST TO REMAIN (Y)	M7200100 INSTALL TYPE 1 (SQ. M)	M7200200 INSTALL TYPE 2 (SQ. M)	P1 (M)	M7280100 PAY LENGTH (M)	TUBULAR TF SIN POST (EACH)	P1 (M)	M7300100 PAY LENGTH (M)	73700100 REM CONC FDN-GR MT SUPPORT (M)	73700200 REM CONC FDN-GR MT (M)	S EN LEN LEG 203 (IN) (SQ M)	S EN LEN LEG 254 (IN) (SQ M)	S EN LEN LEG 318 (IN) (SQ M)	P1 (M)	SIGN POST WOOD (IND (M.)	SIGN POST SQ T1 REINF AN BASE (M.)	SIGN POST SQ T2 REINF AN BASE (M.)	SIGN POST SQ T1 UNREINF AN BASE (M.)	SIGN POST SQ T2 UNREINF AN BASE (M.)	NOTES
IL80-01TS	6+826	CL		1.2	1.50	0.30		0.45		1.3		1.0														
IL80-02TS					1.50	0.30		0.45																		MOUNTED TO BACKSIDE OF IL80-01
IL80-03NW	6+875	RT			1.00	0.25		0.25																		MOUNTED TO NOISE WALL
IL80-04NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-04ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-05NW	6+875	LT			1.00	0.25		0.25																		MOUNTED TO NOISE WALL
IL80-06NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-06ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-07OH	6+952	CL			1.20	0.90			1.08																	MOUNTED TO OVHD SIGN SUPPORT
IL80-08OH					1.20	0.90			1.08																	MOUNTED TO OVHD SIGN SUPPORT
IL80-11NW	6+975	RT			0.70	0.25		0.18																		MOUNTED TO NOISE WALL
IL80-12NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-12ANW					6.00	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-13NW	6+975	LT			0.70	0.25		0.18																		MOUNTED TO NOISE WALL
IL80-14NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-14ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-15NW	7+075	RT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-16NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80.16ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-17NW	7+075	LT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-18NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-18ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-19TS	7+148	CL		1.2	1.50	0.30		0.45		1.3		1.0														MOUNTED ON BARRIER WALL
IL80-20TS					1.50	0.30		0.45																		MOUNTED TO BACKSIDE OF IL80-19
IL80-21NW	7+175	RT			0.90	0.25		0.23																		MOUNTED TO NOISE WALL
IL80-22NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-22ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-23NW	7+175	LT			0.90	0.25		0.23																		MOUNTED TO NOISE WALL
IL80-24NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-24ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-27NW	7+243	LT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-28NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-28ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-29NW	7+275	RT			1.00	0.25		0.25																		MOUNTED TO NOISE WALL
IL80-30NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-30ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-33NW	7+375	RT			1.00	0.25		0.25																		MOUNTED TO NOISE WALL
IL80-34NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-34ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-35NW	7+390	LT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-36NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-36ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-37TS	7+470	CL			1.50	0.30		0.45		1.3		1.0														MOUNTED ON BARRIER WALL
IL80-38TS					1.50	0.30		0.45																		MOUNTED TO BACKSIDE OF IL80-37
IL80-39NW	7+475	RT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-40NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-40ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-42NW	7+733	RT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-43NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-43ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-44TS	7+792	CL			1.50	0.30		0.45		1.3		1.0														MOUNTED ON BARRIER WALL
IL80-45TS					1.50	0.30		0.45																		MOUNTED TO BACKSIDE OF IL80-44
IL80-46NW	7+805	RT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-47NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-47ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-49OH	7+946	CL			1.20	0.90			1.08																	MOUNTED TO OVHD SUPPORT
IL80-50OH					1.20	0.90			1.08																	MOUNTED TO OVHD SUPPORT
IL80-51NW	7+955	RT			1.20	0.25		0.30																		MOUNTED TO NOISE WALL
IL80-52NW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
IL80-52ANW					0.60	0.45		0.27																		MOUNTED TO NOISE WALL
TOTALS								16.45	4.32			4.00	0.00	0.00	0.00	0.00	0.00		0.00			0.00	0.00	0.00	0.00	

NOTE:
"AA" = DISTANCE FROM EDGE OF TRAVELED WAY
"BB" = DISTANCE FROM BOTTOM OF SIGN TO PAVEMENT

SIGN LOCATION SUBJECT TO MINOR RELOCATION IN FIELD AT TIME OF CONSTRUCTION AS DIRECTED BY THE ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41

SIGNING SCHEDULE

SCALE DRAWN BY ACE/CAD
DATE 07/05 CHECKED BY TAE

AMERICAN CONSULTING ENGINEERS