ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	364
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 62114 INDOT DES. NO. 0100987

SIGNING SCHEDULE - GROUND MOUNTED SIGNS

								ILLINOIS SIGN PANELS		STEEL SIGN SUPPORT			WOOD SIGN SUPPORT				INDIANA SIGN PANELS			INDIANA STEEL SIGN SUPPORT						
SIGN NO.	STATION	LT/RT	"AA" (M)	"BB" (M)	WIDTH (M)	DEPTH (M)	EXIST TO REMAIN (Y)	M7200100 INSTALL TYPE 1 (SQ. M)	M7200200 INSTALL TYPE 2 (SQ. M)	P1 (M)	M7280100 PAY LENGTH (M)	TUBULAR TF SIN POST (EACH)	P1 (M)	M7300100 PAY LENGTH (M)	73700100 REM CONC FDN-GR MT SUPPORT (M)	73700200 REM CONC FDN-GR MT (M)	S EN LEN LEG 203 (IN) (SQ M)	S EN LEN LEG 254 (IN) (SQ M)	S EN LEN LEG 318 (IN) (SQ M)	P1 (M)	SIGN POST WOOD (IN) (M.)	SIGN POST SQ T1 REINF AN BASE (M.)	SIGN POST SQ T2 REINF AN BASE (M.)	SIGN POST SQ T1 UNREINF AN BASE (M.)	SIGN POST SQ T2 UNREINF AN BASE (M.)	NOTES
IGDE-01	9+063	RT					N								2	2										
IN80-63NW	9+073	LT			2.00	0.45													0.9							MOUNTED ON FRONTSIDE OF NOISE WALL
IN80-64NW					2.00	0.45													0.9							MOUNTED ON BACKSIDE OF NOISE WALL
IN80-65NW					0.60	0.45												0.27								COVER FOR ACCESS HOLE
IN80-66NW					0.60	0.60												0.36								MOUNTED ON FRONTSIDE OF NOISE WALL
IN80-67NW					0.60	0.60												0.36								MOUNTED ON FRONTSIDE OF NOISE WALL
IN80-68NW					0.60	0.60												0.36								MOUNTED ON BACKSIDE OF NOISE WALL
IN80-69NW					0.60	0.60												0.36								MOUNTED ON BACKSIDE OF NOISE WALL
IN80-70TS	9+079	CL			1.50	0.38						1.0						0.563								
IN80-71TS					1.50	0.38												0.563								MOUNTED ON BACKSIDE OF IN80-70TS
IN80-72WP	9+103	LT	3.48	2.1	1.20	1.20													1.44	5.5	5.5					
IN80-73WP	9+138	LT	1.80	2.1	1.20	1.20													1.44	5.5	5.5					
IN80-74TS	9+240	CL			1.50	0.38						1.0						0.563								
IN80-75TS					1.50	0.38												0.563								MOUNTED ON BACKSIDE OF IN80-74TS
IN80-76TS	9+197	RT	22.18	2.1	1.80	1.80													3.24	5.5	5.5					
IN80-77TS	9+401	CL			1.50	0.38						1.0						0.563								
IN80-78TS					1.50	0.38												0.563								MOUNTED ON BACKSIDE OF IN80-77TS
IN80-79TS	9+562	CL			1.50	0.38						1.0						0.563								
IN80-80TS					1.50	0.38												0.563								MOUNTED ON BACKSIDE OF IN80-79TS
IN80-81TS	9+723	CL			1.50	0.38						1.0						0.563								
IN80-82TS					1.50	0.38												0.563								MOUNTED ON BACKSIDE OF IN80-81TS
TOTALS								0.00	0.00			8.00		0.00	2.00	2.00	0.00	23.77	30.18		27.30	0.00	0.00	0.00	0.00	

NOTE:
"AA" = DISTANCE FROM EDGE OF TRAVELED WAY
"BB" = DISTANCE FROM BOTTOM OF SIGN TO PAVEMENT

SIGN LOCATION SUBJECT TO MINOR RELOCATION IN FIELD AT TIME OF CONSTRUCTION AS DIRECTED BY THE ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41

SIGNING SCHEDULE

SCALE DRAWN BY ACE/CAD
DATE 07/05 CHECKED BY TAE

AMERICAN CONSULTING ENGINEERS