

F.A.R. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
STA. J16R-4	DEKALB	416	48
STA. TO STA.			
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT	

78100100	RAISED REFLECTIVE PAVEMENT MARKERS (CONT.)				REMARKS
EACH	LOCATION				
14	US 30	807+55.55	TO	809+69.52	TWO-WAY AMBER
9		809+71.56	TO	810+66.19	ONE-WAY AMBER
7		860+12.70	TO	862+68.29	ONE-WAY CRYSTAL
11		861+62.30	TO	862+62.84	ONE-WAY AMBER
4		863+06.02	TO	864+21.02	ONE-WAY CRYSTAL
8		863+06.02	TO	864+21.03	TWO-WAY AMBER
22		864+21.02	TO	868+64.90	ONE-WAY AMBER
SUBTOTAL					
186.0					
9	S. SOMONAUK RD.	18+49.20	TO	19+68.67	ONE-WAY AMBER
10	N. SOMONAUK RD.	30+38.98	TO	31+47.68	TWO-WAY AMBER
SUBTOTAL					
19.0					
TOTAL					
205.0					

78200410	GUARDRAIL MARKERS, TYPE A				REMARKS
EACH	LOCATION				
	US 30				
1		LT 785+97.15			
1		LT 786+77.15			
1		LT 787+57.15			
1		RT 786+37.17			
1		RT 787+17.17			
1		RT 787+97.17			
TOTAL					
6					

78300100	PAVEMENT MARKING REMOVAL				REMARKS
SQ. FT.	LOCATION				
	US 30				
	STAGE 2				
100.0	CENTERLINE	795+00.00	TO	801+00.00	SKIP DASH
156.7	RT EDGE LINE	795+00.00	TO	799+70.00	
63.3	RT EDGE LINE	801+50.00	TO	803+40.00	
23.3	RT EDGE LINE	810+40.00	TO	811+10.00	
20.0	RT EDGE LINE	814+40.00	TO	815+00.00	
10.0	RT EDGE LINE	818+90.00	TO	819+20.00	
28.3	RT EDGE LINE	823+00.00	TO	823+85.00	
323.3	PARKING LINE	823+25.00	TO	833+00.00	
125.0	CENTERLINE	833+75.00	TO	841+25.00	SKIP DASH
41.7	LT EDGE LINE	840+00.00	TO	841+25.00	
	STAGE 5				
1175.0	LT EDGE LINE	841+25.00	TO	876+50.00	
37.5	CENTERLINE	872+00.00	TO	876+50.00	SKIP DASH
	STAGE 6				
61.7	LT EDGE LINE	834+15.00	TO	836+00.00	
15.4	CENTERLINE	834+15.00	TO	836+00.00	SKIP DASH
61.7	RT EDGE LINE	834+15.00	TO	836+00.00	
TOTAL					
2242.9					

X0300351	CONCRETE STEP REMOVAL				REMARKS
EACH	LOCATION				
	US 30				
1		LT 828+55.00			
1		LT 828+68.00			
1		LT 828+81.90			
1		LT 829+16.00			
1		LT 830+44.30			
1		LT 831+78.00			
1		LT 831+88.00			
1		LT 832+01.00			
1		LT 833+11.00			
	N Oak				
1		RT 181+20.66			
TOTAL					
10					

X0322118	REMOVE CONCRETE FLARED END SECTIONS				REMARKS
EACH	LOCATION				
1		RT 803+71.00			
1		LT 803+71.00			
TOTAL					
2					

X0322782	SANITARY SEWER, PVC (D3034) SDR 26, 8"				REMARKS
FOOT	LOCATION				
75		RT 813+91.00	TO	814+66.00	SANITARY SEWER
40		RT 819+09.00	TO	819+41.00	SANITARY SEWER
TOTAL					
115					

X0322903	SAW CUTTING, (FULL DEPTH)				REMARKS
FOOT	LOCATION				
144		RT 802+32.80	TO	802+60.50	ISLAND REMOVAL AND REPLACEMENT
TOTAL					
144					

X0539800	TREE GRATES				REMARKS
EACH	LOCATION				
	US 30				
1		RT 824+80.00			
1		LT 825+53.00			
1		RT 827+66.00			
1		LT 827+84.00			
1		RT 828+93.00			
1		LT 831+13.00			
1		RT 831+42.00			
1		RT 832+15.00			
1		LT 832+23.00			
TOTAL					
9					

X0712400	TEMPORARY PAVEMENT				REMARKS
SQ. YD.	LOCATION				
	US 30				
	STAGE 1				
337.92	12 INCH	799+63.66	TO	801+83.50	TEMP PAVEMENT RT
1666.29	12 INCH	802+85.00	TO	810+61.73	TEMP PAVEMENT RT
692.71	12 INCH	810+94.09	TO	814+58.06	TEMP PAVEMENT RT
782.62	12 INCH	814+89.33	TO	818+88.25	TEMP PAVEMENT RT
573.07	12 INCH	819+11.03	TO	823+03.10	TEMP PAVEMENT RT
522.48	12 INCH	832+73.16	TO	837+09.06	TEMP PAVEMENT RT
199.80	12 INCH	837+58.57	TO	841+25.00	TEMP PAVEMENT RT
	STAGE 2				
368.44	12 INCH	799+45.71	TO	803+03.00	RUN-AROUND
864.34	12 INCH	837+93.63	TO	841+64.70	TEMP PAVEMENT LT
	STAGE 4				
1353.27	12 INCH	841+91.62	TO	847+75.18	TEMP PAVEMENT LT
999.43	12 INCH	848+35.28	TO	852+51.60	TEMP PAVEMENT LT
701.16	12 INCH	852+97.83	TO	855+90.35	TEMP PAVEMENT LT
635.33	12 INCH	856+41.44	TO	859+12.27	TEMP PAVEMENT LT
3111.75	12 INCH	860+03.31	TO	876+25.00	TEMP PAVEMENT LT
TOTAL					
12,808.6					

X0919000	TEMPORARY PAVEMENT REMOVAL				REMARKS
SQ. YD.	LOCATION				
	US 30				
	STAGE 1				
337.92	12 INCH	799+63.66	TO	801+83.50	TEMP PAVEMENT RT
1666.29	12 INCH	802+85.00	TO	810+61.73	TEMP PAVEMENT RT
692.71	12 INCH	810+94.09	TO	814+58.06	TEMP PAVEMENT RT
782.62	12 INCH	814+89.33	TO	818+88.25	TEMP PAVEMENT RT
573.07	12 INCH	819+11.03	TO	823+03.10	TEMP PAVEMENT RT
522.48	12 INCH	832+73.16	TO	837+09.06	TEMP PAVEMENT RT
199.80	12 INCH	837+58.57	TO	841+25.00	TEMP PAVEMENT RT
	STAGE 2				
368.44	12 INCH	799+45.71	TO	803+03.00	RUN-AROUND
864.34	12 INCH	837+93.63	TO	841+64.70	TEMP PAVEMENT LT
	STAGE 4				
1353.27	12 INCH	841+91.62	TO	847+75.18	TEMP PAVEMENT LT
999.43	12 INCH	848+35.28	TO	852+51.60	TEMP PAVEMENT LT
701.16	12 INCH	852+97.83	TO	855+90.35	TEMP PAVEMENT LT
635.33	12 INCH	856+41.44	TO	859+12.27	TEMP PAVEMENT LT
3111.75	12 INCH	860+03.31	TO	876+25.00	TEMP PAVEMENT LT
TOTAL					
12,808.6					

PLOT DATE = Fri, Sep 02 09:31:27 2005
 FILE NAME = C:\p\projects\0201760\c081708rev.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = jward