CONTRACT NO. 64594

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129K	WINNEBAGO	585	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

BITUMINOUS SCHEDULE

				PAVEMENT/SHOULDERS						PRIME COAT		REMOVAL			
				X4066414	X4066426	X4074126	40800040	48202400	48202500	40600200	40600300	44000100	44000920	44004250	44213200
				BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX "C" N50	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX "D" N70	POLYMERIZED BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 12 1/4"	INCIDENTAL BITUMINOUS SURFACING	BITUMINOUS SHOULDERS SUPERPAVE 6"	BITUMINOUS SHOULDERS SUPERPAVE 7"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	PAVEMENT REMOVAL	BITUMINOUS CONCRETE SHOULDER REMOVAL	PAVED SHOULDER REMOVAL	SAW CUTS
STATION	OFF	STATION	OFF	TON	TON	SQ YD	TON	SQ YD	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	FOOT
IL 173															
142+00.00		148+00.00										1512.4			
142+33.00		156+00.00				7568									
142+34.20	12' RT	143+97.10	12' RT	11				99							
142+34.20	12' LT	150+53.90	12' LT	89				792							
148+00.00		154+00.00										1600			
154+00.00		159+12.00										1797			
156+00.00		174+42.00				17798.6									
159+12.00		162+00.00										2128			
166+00.00		172+00.00										1539			
172+00.00		178+00.00										1792			
174+42.00		186+52.00				12086.9									
184+00.00		190+00.00										1668			
186+52.00		197+95.00				10500.5									
190+00.00		196+00.00										1600			
191+54.00		193+03.90					32								
196+00.00		202+00.00										1600			
197+95.00		211+39.00				12076.5									
202+00.00		208+00.00										1600			
208+00.00		214+00.00										1600			
209+11.00	12.5' LT												33.8		
211+39.00		222+95.00				9513.3									
214+00.00		220+00.00										1600			
218+40.90	12' LT	232+12.80	12' LT	159				1417							
218+40.90	12' RT	232+12.90	12' RT	156				1396							
220+00.00		226+00.00										1600			
222+95.00		231+14.00				3387.6									
226+00.00		231+14.00										1371			
I-90															
410+96.78	50.30' LT	442+44.07	50.47' LT											3602	3147
421+00.00	49.50' RT	421+00.00	60.44' RT		0.9			8						8	
421+00.00	24.65' RT	421+00.00	13.58' RT		0.9			8						8	
421+00.00	25.50' LT	421+00.00	14.20' LT		0.9			8						8	
421+85.21	49.50' RT	429+02.50	50.30' RT											897	717
424+00.00	14.16' LT	424+00.00	25.50' LT		0.9			8						8	
430+00.00	13.78' LT	430+00.00	25.50' LT		0.9			8						8	
441+45.11	24.70' RT	442+24.39	24.80' LT											93	79
441+45.14	49.90' RT	442+13.09	50.00' RT											84	68
441+50.99	50.50' RT	442+27.95	50.50' RT		11.3			101							
441+50.99	13.50' RT	442+39.38	13.50' RT		15.2			136							
441+51.11	49.90' RT	442+20.73	24.80' RT									184			
441+64.26	25.40' LT	442+36.47	25.30' LT											95	72
441+70.23	25.30' LT	442+43.64	50.50' LT									195			
441+70.29	13.50' LT	442+47.72	13.50' LT		12.7			113							
441+97.84	50.50' RT	445+86.70	50.50' RT		13.6			121							
444+09.44	50.00' RT	445+86.70	24.90' RT									483			
444+09.44	50.14' RT	445+92.70	49.90' RT											235	184
444+17.00	25.00' RT	445+92.70	25.90' RT											214	176
444+32.85	25.06' LT	446+10.17	50.09' LT									478			
444+32.85	25.10' LT	446+16.17	25.17' LT											230	183
444+40.34	49.74' LT	454+84.43	50.00' LT											1279	1044
445+09.27	13.50' RT	445+86.70	13.50' RT		12.7			113							
445+17.61	13.50' LT	446+10.17	13.50' LT		15.9			142							
450+00.00	14.07' LT	450+00.00	25.16' LT		0.9			8						8	
454+84.43	50.00' LT	468+14.21	49.72' LT		181.9				1624					1624	1330
457+41.43	50.26' RT	482+57.91	50.30' RT											3091	2517
468+14.21	49.72' LT	476+58.66	50.30' LT											1005	845
474+09.20	13.75' LT	474+55.43	25.16' LT		6.6			59						59	
RAMP A															
799+90.00	0.00' RT	808+38.30	0.00' RT		105.2			939							
800+12.06	0.00' RT	808+38.30	0.00' RT			1935									
808+38.30	0.00' RT	831+48.75	0.00' RT		287.4			2566							
808+38.30	0.00' RT	831+73.75	0.00' RT			5062									
808+38.30	16.00' LT	831+73.75	16.00' LT		115.8			1034							
831+00.00	16' LT	831+34.00	16' LT	1				12		0.01	0.2				
831+00.00	20' RT	831+74.00	20' RT	9				78		0.05	1.2				
831+17.68	16.00' LT	831+33.97	16.00' LT		0.4			4							
831+48.75	0.00' RT	831+73.75	0.00' RT		2.6			23							
Ramp A & B						1529.3				1.4	9.2				
SUB-TOTAL				425	786.588	81457.7	32	9193	1624	1.46	10.6	24347.4	33.8	12556	10362

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. N/A HORIZ. N/A

DATE SEPTEMBER 14, 2005

DRAWN BY KRL

CHECKED BY PDS