

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONCRETE SCHEDULE

STATION	OFF	STATION	OFF	BRIDGE APPROACH		PATCHES		BARRIER / MEDIANS / ISLANDS			REMOVAL						
				44000700	X0321430	44201078	44201080	44201294	63700600	60618300	60620300	*2001364	44002805	44003100	44003700	44004000	
				APPROACH SLAB REMOVAL	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL	CLASS B PATCHES TYPE III	CLASS B PATCHES TYPE IV	CLASS B PATCH - EXPANSION JOINT	CONCRETE BARRIER, SINGLE FACE (SPECIAL)	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SB-6.24 (SPECIAL)	P.C.C. RAMPED MEDIAN TERMINAL SPECIAL	ISLAND REMOVAL	MEDIAN REMOVAL	MEDIAN REMOVAL (SPECIAL)	PAVED DITCH REMOVAL	
				SQ YD	SQ YD	SQ YD	SQ YD	FOOT	FOOT	SQ FT	SQ FT	SQ YD	SQ FT	SQ FT	SQ FT	FOOT	
IL 173																	
151+08.94	2' LT	151+29.64	2' RT									30.8					
151+21.60		156+71.80								10851				2321			
154+90.00		159+12.00															
156+71.80		159+93.20									2560			142			
159+12.00	9' RT	160+24.00	2' LT														
159+73.65	5' RT	160+23.20	5' RT							1534							
159+82.82	11' LT	159+88.80	11' LT									2.5					
159+90.34	RT	160+22.64	RT										868				
160+24.25	82.0' RT	160+24.25	140' RT												216		
160+38.30	35' RT	160+55.80	35' RT											1848			
160+49.80	59' RT	160+50.30	53' RT									4.7					
160+70.18	RT	160+87.01	RT										206				
161+33.44	10' RT	161+39.50	10' RT									2.8					
161+34.90		164+17.80															
164+17.80		176+33.90								29172		2405					
176+33.90		180+20.30										3192					
180+18.30	12' LT	180+24.30	12' LT									4.6					
181+06.60	10' LT	181+13.10	58									6.5					
181+10.40		181+12.90										56					
181+12.90		193+86.20															
191+58.90	57.5' RT	194+16.50	57.4' RT						258								
193+85.00		195+85.80										1586					
195+79.90	10' LT	195+87.70	10' LT									3.4					
197+11.90	12' LT	197+17.90	11' LT									5.2					
197+19.40		208+87.80								29247							
208+87.80		211+39.30										1994					
211+35.10	10' LT	211+41.10	10' LT									2.5					
213+02.70	10' RT	213+08.70	10' RT									2.5					
213+04.56		215+56.10															
215+56.10		222+84.40															
222+84.40	4' RT	223+03.70	4' RT							17029		37.4					
I-90																	
421+00.00	25.20' RT	421+00.00	49.50' RT														
421+00.00	25.20' LT	421+00.00	50.30' LT														
424+00.00	25.5' LT	424+00.00	50.40' LT														
430+00.00	25.5' LT	430+00.00	50.40' LT														
441+45.11	49.90' RT	441+51.11	24.70' RT														
441+50.99	50.5' RT	442+39.38	13.50' RT		340												
441+64.26	25.30' LT	441+70.26	50.30' LT														
441+70.29	13.50' LT	442+63.20	63.64' LT														
442+09.30	61.54' RT	442+56.04	13.04' RT														
442+32.70	13.10' LT	442+78.48	60.50' LT														
443+74.06	61.95' RT	444+20.61	14.04' RT														
443+97.59	12.98' LT	444+44.06	61.78' LT														
444+97.84	50.5' RT	445+86.70	13.50' RT														
445+17.61	13.50' LT	446+10.17	65.76' LT														
445+86.70	49.90' RT	445+92.72	24.90' RT														
446+10.17	25.20' LT	446+16.17	50.10' LT														
450+00.00	25.20' LT	450+00.00	49.70' LT														
474+09.20	25.20' LT	474+55.43	50.060' LT														
477+00.68	87.52' RT	481+18.45	133.32' RT													421	
TOTAL					446	1641	153	128	250	258	118729	13787	103	1074	5311	216	421

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES SCALE: VERT. N/A HORIZ. N/A DATE: SEPTEMBER 14, 2005	DRAWN BY: KRL CHECKED BY: PDS
NAME	DATE		