CONTRACT NO. 64594

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129K	WINNEBAGO	585	34
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

STORM AND SANITARY SEWER SCHEDULE

				STORM SEWERS / TRENCH BACKFILL																		
				60107600	60107700	20800150	550A0050	550A0070	550A0090	550A0120	550A0340	550A0360	550A0380	550A0410	550A0430	550A0450	550A0470	550A0480	550A0490	550A0500	550A0680	XX005296
				PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 6"	TRENCH BACKFILL	STORM SEWERS, CLASS A, TYPE 1 12"	STORM SEWERS, CLASS A, TYPE 1 15"	STORM SEWERS, CLASS A, TYPE 1 18"	STORM SEWERS, CLASS A, TYPE 1 24"	STORM SEWERS, CLASS A, TYPE 2 12"	STORM SEWERS, CLASS A, TYPE 2 15"	STORM SEWERS, CLASS A, TYPE 2 18"	STORM SEWERS, CLASS A, TYPE 2 24"	STORM SEWERS, CLASS A, TYPE 2 30"	STORM SEWERS, CLASS A, TYPE 2 36"	STORM SEWERS, CLASS A, TYPE 2 42"	STORM SEWERS, CLASS A, TYPE 2 48"	STORM SEWERS, CLASS A, TYPE 2 54"	STORM SEWERS, CLASS A, TYPE 2 60"	STORM SEWERS, CLASS A, TYPE 3 18"	STEEL CASING PIPE 36"
STATION	OFFSET	STATION	OFFSET	FOOT	FOOT	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
IL 173																						
205+00.00	0'	205+00.00	52.0' RT									53										
205+00.00	52.0' LT	207+00.00	52.0' LT											194								
207+00.00	52.0' LT	207+00.00	0'									53										
207+00.00	0'	207+00.00	52.0' RT									53										
207+00.00	52.0' LT	209+00.00	52.0' LT										194									
209+00.00	52.0' LT	209+00.00	5.4' LT									48										
209+00.00	5.4' LT	209+00.00	52.0' RT									60										
211+50.00		217+00.00		306																		
214+00.00	8.0' RT	214+00.00	52.0' RT								45											
214+00.00	52.0' LT	214+00.00	8.0' RT								63											
214+00.00	52.0' LT	216+00.00	52.0' LT									194										
216+00.00	52.0' LT	216+00.00	0.6' LT								53											
216+00.00	0.6' LT	216+00.00	52.0' RT								53											
216+00.00	52.0' LT	218+00.00	52.0' LT										189									
217+89.00		218+00.00				31.1																
218+00.00		218+14.00				36.7																
218+00.80	0'	219+00.00	0'									97										
219+00.00	0'	220+00.00	1.8' RT								97											
220+00.00	1.8' RT	221+00.00	3.1' RT								97											
I-90																						
410+96.78	49.50' LT	442+66.29	63.00' LT		3150																	
411+50.00	62.0' LT		87.0' LT				23															
412+00.00	65.0' LT		92.5' LT				26															
414+00.00	72.0' LT		100.0' LT				26															
416+00.00	73.0' LT		104.0' L				29															
418+00.00	73.0' LT		110.8' L				36															
420+00.00	73.0' LT		117.2' L				42															
421+00.00	80' RT		110' LT			68.8																
422+00.00	73.0' LT		121.0' L				46															
424+00.00	0' LT		73' LT			16.1																
424+00.00	0' LT		73' LT					72														
424+00.00	73' RT		120' LT						45													
426+00.00	73.0' LT		108.1' L				38															
428+00.00	73.0' LT		101.1' L				25															
430+00.00	0' LT		73' LT			7.1																
430+00.00	73' LT		103.3' LT					28														
430+00.00	0' LT		73' LT					72														
432+00.00	73.0' LT		108.1' L				29															
434+00.00	73.0' LT		107.0' L				33															
436+00.00	73.0' LT		101.0' L				25															
438+00.00	73.0' LT		102.5' L				27															
440+00.00	73.0' LT		100.9' L				25															
442+00.00	2' LT		75' LT			15.5																
442+00.00	62.5' RT		101.0' RT					36														
446+00.00	75.3' LT		185' LT						110													
447+00.00	77.3' LT		182.5' L				102															
449+00.00	93.0' LT		197.8' L				109															
450+00.00	0' LT		88' LT			10.2																
450+00.00	0' LT							82														
450+00.00			82' RT						112													
451+00.00	85.3'LT		195.2' L				107															
453+00.00	91.4' LT		198.3' L				105															
459+00.00	75.0' RT		105.4' L				29															
460+84.05	73.69' LT	482+58.33	60.86' LT		2179																	
461+00.00	73.0' RT	461+25.00	82' RT				24															
461+25.00	82' RT	463+00.00	82' RT				172															
463+00.00	82' RT	465+00.00	73' RT						197													
463+00.00	73' RT		82' RT						7													
465+00.00	73' RT	467+00.00	82' RT						200													
465+00.00	73' RT		82' RT						7													
467+00.00	82' RT	469+00.00	82' RT							197												
467+00.00	73' RT		82' RT						7													
469+00.00	82' RT	471+00.00	82' RT							197												
469+00.00	73' RT		82' RT						7													
471+00.00	82' RT	471+75.00	82' RT							72												
471+00.00	73' RT		82' RT						7													
471+75.00	82' RT	472+60.00	127.27 RT							94												
473+00.00	73.0' RT		117.0' RT				42															
474+00.00	0' LT	474+98.00	95.0' LT						143													
474+00.00	0' LT		70' LT			12.1																
SUB-TOTAL				306	5329	197.6	1120	290	842	560	408	558	383	194	0	0	0	0	0	0	0	0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. N/A HORIZ. N/A

DATE SEPTEMBER 14, 2005

DRAWN BY KRL

CHECKED BY PDS