

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	36
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM AND SANITARY SEWER SCHEDULE

				CULVERTS											
				540I0506	542A1069	542A1075	542A1081	542A1087	542A1095	542A1123	542D0223	542D0229	542D1069	542D3427	542D9901
				PRECAST CONCRETE BOX CULVERT 5' X 6'	PIPE CULVERTS, CLASS A, TYPE 2 24"	PIPE CULVERTS, CLASS A, TYPE 2 30"	PIPE CULVERTS, CLASS A, TYPE 2 36"	PIPE CULVERTS, CLASS A, TYPE 2 42"	PIPE CULVERTS, CLASS A, TYPE 2 60"	PIPE CULVERTS, CLASS A, TYPE 2 78"	PIPE CULVERTS, CLASS D, TYPE 1 18"	PIPE CULVERTS, CLASS D, TYPE 1 24"	PIPE CULVERTS, CLASS D, TYPE 2 24"	PIPE CULVERTS, CLASS D, TYPE 5 72"	PIPE CULVERTS TYPE 2, RC-E, EQUIVALENT ROUND SIZE 36"
STATION	OFFSET	STATION	OFFSET	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
IL 173															
142+50.00	22.5' RT	142+50.00	26.2' LT												49
142+50.00	108.2' LT	142+50.00	40.0' LT												68
148+87.20	112.0' LT	149+01.40	32.7' RT						141						
159+33.30	110.0' RT	161+32.00	110.0' RT										198		
212+70.50	94.1' RT	213+00.00	77.8' RT		35										
213+00.00	74.0' LT	213+00.00	77.8' RT		35										
217+86.00	77.0' LT	217+89.40	62.5' LT					15							
217+89.40	57.5' LT	218+00.00	2.5' LT					56							
218+00.00	2.5' RT	218+14.00	66.5' RT					66							
I-90															
421+00.00	80' RT		110' LT			190									
453+00.00	98.3' LT		198.0' LT											99.7	
RAMP A															
824+00.00	135.0' LT		42.1' RT		177										
RAMP B															
5012+88.00	67.2' LT		51.0' RT				118								
RAMP C															
4009+69.60	41.5' RT	4010+57.10	52.7' LT							130					
LYFORD ROAD															
2001+00.00	44.0' RT	2001+00.00	39.0' LT									83			
GREENLEE DRIVEWAY															
17+50.00	19.9' LT	17+50.00	20.5' RT									40			
BIKEPATH															
558+90.00	14.0' LT	558+90.00	14.0' LT								28				
571+79.00	14.0' LT	571+79.00	14.0' LT								28				
580+84.60	14.0' LT	580+84.60	14.0' LT								28				
583+90.40	14.0' LT	583+90.40	14.0' LT								28				
TOTAL				177	70	190	118	137	141	130	112	123	198	100	117

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. N/A
 HORIZ. N/A
 DATE: SEPTEMBER 14, 2005
 DRAWN BY: KRL
 CHECKED BY: PDS