

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	38
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

## STORM AND SANITARY SEWER SCHEDULE

STATION	OFFSET	STRUCTURES											
		60242400 INLET SPECIAL EACH	60242500 INLET SPECIAL NO. 1 EACH	60242600 INLET SPECIAL NO. 2 WITH FRAME AND GRATE EACH	60242700 INLETS, SPECIAL, NO. 3 EACH	60242801 INLETS, SPECIAL, NO. 5 EACH	60246541 INLETS BOX SPECIAL NO. 1 EACH	60246542 INLETS BOX SPECIAL NO. 2 EACH	*2001350 SLOPE DRAIN INLET EACH	*2001316 CATCH BASIN TYPE B WITH FRAME & GRATE EACH	*2001317 CATCH BASIN TYPE G-2 WITH TYPE G-2 FRAME & GRATE EACH	*2001318 CATCH BASIN TYPE G-3 WITH TYPE G-3 FRAME & GRATE EACH	*2001360 CATCH BASIN TYPE M-2 WITH FRAME & GRATE EACH
IL 173													
199+50.00	64.0' LT												
199+50.00	52.0' RT												
201+00.00	59.3' LT												
201+00.00	52.0' RT												
203+00.00	52.0' LT												
203+00.00	52.0' RT												
205+00.00	52.0' LT												
205+00.00	52.0' RT												
207+00.00	52.0' LT												
207+00.00	52.0' RT												
209+00.00	5.4' LT												
209+00.00	5.4' RT												
209+00.00	52.0' LT												
209+00.00	52.0' RT												
214+00.00	8.0' RT												
214+00.00	8.0' RT												
214+00.00	52.0' RT												
214+00.00	52.0' LT												
216+00.00	0.6' LT												
216+00.00	0.6' LT												
216+00.00	52.0' LT												
216+00.00	52.0' RT												
218+15.00	32.7' RT												
I-90													
411+50.00	62.0' LT												
412+00.00	65.0' LT												
414+00.00	72.0' LT												
416+00.00	73.0' LT												
418+00.00	73.0' LT												
420+00.00	73.0' LT												
422+00.00	73.0' LT												
424+00.00	73.0' LT												
426+00.00	73.0' LT												
428+00.00	73.0' LT												
430+00.00	73.0' LT												
432+00.00	73.0' LT												
434+00.00	73.0' LT												
436+00.00	73.0' LT												
438+00.00	73.0' LT												
440+00.00	73.0' LT												
442+00.00	62.5' RT												
442+00.00	0.0'												
442+00.00	76.0' LT												
446+00.00	75.3' LT												
447+00.00	77.3' LT												
449+00.00	93.0' LT												
450+00.00	83.8' LT												
451+00.00	85.3' LT												
453+50.00	91.4' LT												
459+00.00	75.0' RT												
461+00.00	73.0' RT												
463+00.00	73.0' RT												
465+00.00	73.0' RT												
467+00.00	73.0' RT												
469+00.00	73.0' RT												
471+00.00	73.0' RT												
473+00.00	73.0' RT												
475+00.00	73.0' RT												
477+00.00	73.0' RT												
479+00.00	79.2' RT												
481+00.00	66.4' RT												
482+00.00	62.4' RT												
RAMP A													
808+50.00	27.5' LT												
809+00.00	10.0' RT												
812+00.00	10.0' RT												
814+00.00	10.0' RT												
822+00.00	20.0' LT												
824+00.00	46.0' LT												
SUB-TOTAL		0	0	6	5	11	0	1	10	3	5	25	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. N/A  
 HORIZ. N/A  
 DATE: SEPTEMBER 14, 2005

DRAWN BY: KRL  
 CHECKED BY: PDS