

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	42
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM AND SANITARY SEWER SCHEDULE

STATION	OFFSET	END SECTIONS									HEADWALLS								
		54002020	54213453	54213459	54213657	54213669	54213687	54213705	54214521	54215472	54215478	*2001347	*2001348	*2001349	XX005381	*2001367	*2001352	*2001353	*2001331
		EXPANSION BOLTS 3/4 INCH EACH	END SECTIONS, 18' EACH	END SECTIONS, 24' EACH	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12' EACH	PRECAST REINFORCED CONCRETE SECTIONS, 24' EACH	PRECAST REINFORCED CONCRETE SECTIONS, 42' EACH	PRECAST REINFORCED CONCRETE SECTIONS, 60' EACH	PRC FLARED END SECTIONS, EQUIVALENT ROUND SIZE 36' EACH	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 72' EACH	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 78' EACH	SLOPED HEADWALL TYPE 1, 12' EACH	SLOPED HEADWALL TYPE 1, 15' EACH	SLOPED HEADWALL TYPE 1, 18' EACH	SLOPED HEADWALL TYPE 1, 24' EACH	SLOPED HEADWALL TYPE 3, 6' EACH	HEADWALL TYPE 1, 24' EACH	HEADWALL TYPE 1, 30' EACH	HEADWALL, TYPE 4 EACH
RAMP B																			
5008+74.75	74.4 RT																		
5008+74.75	98.0 RT																		
5008+76.75	74.4 RT																		
5008+76.75	98.0 RT																		
5010+00.00	30.0' RT																		
5011+50.00	59.7' RT																		
5012+88.00	67.2' LT																		
5012+88.00	51.0 RT																		
5013+50.00	58.2' RT																		
5015+00.00	59.0' RT																		
5017+00.00	74.6' RT																		
5018+59.16	96.7' RT																		
5018+95.30	29.5' LT	8																	
5019+00.00	96.7' RT																		
RAMP C																			
4003+20.00	47.4' LT																		
4006+58.00	52.9' LT																		
4009+00.00	69.7' LT																		
4009+69.6	41.5' RT																		
4010+57.1	52.7' LT																		
4014+00.00	67.6' RT																		
4016+00.00	52.4' RT																		
4034+70.00	52.84' RT																		
4034+95.00	53.36 RT																		
RAMP D																			
1302+00.00	51.25' RT																		
1306+81.00	41.0' RT																		
1309+79.40	42.6' RT																		
1311+68.00	71.78 RT																		
1311+91.00	82.79 RT																		
1315+00.00	34.42' RT																		
1320+00.00	45.64' RT																		
LYFORD ROAD																			
2001+00.00	44.0' RT																		
2001+00.00	39.0' LT																		
BIKEPATH																			
558+90.00	14' LT																		
558+90.00	14' RT																		
571+79.00	14' LT																		
571+79.00	14' RT																		
580+84.60	14' LT																		
580+84.60	14' RT																		
583+90.40	14' LT																		
583+90.40	14' RT																		
SUB-TOTAL		8	8	2	0	0	0	0	0	0	2	19	1	0	0	3	2	0	2
TOTAL		24	8	4	6	2	1	2	3	1	2	52	4	4	1	7	2	2	4

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE: VERT. N/A HORIZ. N/A DATE: SEPTEMBER 14, 2005</p> <p align="right">DRAWN BY: KRL CHECKED BY: PDS</p>