

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	44
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EROSION CONTROL SCHEDULE

				MISC										RIPRAP			
				25000210	25000312	25000314	25000400	25000500	25000600	25100115	25100630	28000300	28000400	28000500	X0323260	28100107	28200100
				SEEDING, CLASS 2A	SEEDING, CLASS 4A	SEEDING, CLASS 4B	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	SEDIMENT BASINS	STONE RIPRAP, CLASS A4	FILTER FABRIC FOR USE WITH RIPRAP
STATION	OFF	STATION	OFF	ACRE	ACRE	ACRE	POUND	POUND	POUND	ACRE	SQ YD	EACH	FOOT	EACH	EACH	SQ YD	SQ YD
IL 173																	
142+32.87		231+14.10		13.75			1237.5	1237.5	1237.5	13.75							
142+32.87	RT	147+33.00	RT								1218						
142+50.00	33' LT	148+00.00	33' LT								489			2			
142+50.00	LT															4	4
142+50.00	LT															30.3	30.3
143+00.00	26' RT	147+50.00	33' RT								400						
143+00.00	LT&RT											2					
143+10.00	LT&RT											2					
143+20.00	LT&RT											2					
143+30.00	LT&RT											2					
143+40.00	LT&RT											2					
143+50.00	LT&RT											2					
144+00.00	LT&RT											2					
144+50.00	LT&RT											2					
145+00.00	LT&RT											2					
145+50.00	LT&RT											2					
146+00.00	LT&RT											2					
146+30.00	LT	148+20.00	LT										200				
146+50.00	LT&RT											2					
147+00.00	LT											1					
147+50.00	LT											1					
148+87.20	LT															30.3	30.3
149+00.00	LT	179+50.00	LT										3060				
149+00.00	RT													1			
149+25.00	RT															1.8	1.8
150+50.00	RT															1.8	1.8
151+70.00	RT	159+75.00	RT								452						
152+00.00	RT															1.8	1.8
154+00.00	RT															1.8	1.8
156+00.00	RT															1.8	1.8
157+50.00	LT	179+50.00	LT										2230				
158+00.00	RT															1.8	1.8
159+33.30	RT															30.3	30.3
161+23.00	RT	167+00.00	RT								335						
161+25.00	RT													1			
167+00.00	RT	184+50.00	RT										1750				
181+80.00	LT	190+00.00	LT								9000		820				
185+50.00	77' RT	190+00.00	69' RT								300						
186+00.00	RT																
186+50.00	RT																
186+75.00	LT															50	50
187+00.00	RT																
187+50.00	RT																
188+00.00	RT																
188+50.00	RT																
189+00.00	RT																
189+10.00	RT																
189+20.00	RT																
190+00.00	RT	191+29.00	RT													96.9	96.9
191+56.20	RT																
197+55.00	RT	203+00.00	RT											1			
198+25.00	103' RT	209+75.00	96' RT													813	813
198+84.00	RT	211+75.00	RT								1022						
199+10.00	RT										735						
199+40.00	RT																
199+60.00	RT																
200+00.00	RT																
200+30.00	RT																
200+60.00	RT																
201+00.00	RT																
201+30.00	RT																
201+60.00	RT																
202+00.00	RT																
202+30.00	RT																
202+60.00	RT																
203+00.00	RT																
203+30.00	RT																
203+60.00	RT																
204+00.00	RT																
204+30.00	RT																
SUB-TOTAL				13.75	0	0	1237.5	1238	1237.5	13.75	13951	52	8060	5	0	1065.6	1065.6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. N/A
 HORIZ. N/A
 DATE: SEPTEMBER 14, 2005

DRAWN BY: KRL
 CHECKED BY: PDS