

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129K	WINNEBAGO	585	46
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EROSION CONTROL SCHEDULE

STATION	OFF	STATION	OFF	25000210	25000312	25000314	25000400	25000500	25000600	MISC		28000300	28000400	28000500	X0323260	28100107	28200100
				SEEDING, CLASS 2A ACRE	SEEDING, CLASS 4A ACRE	SEEDING, CLASS 4B ACRE	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHOROUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	MULCH METHOD 2 ACRE	EROSION CONTROL BLANKET SQ YD	TEMPORARY DITCH CHECKS EACH	PERIMETER EROSION BARRIER FOOT	INLET AND PIPE PROTECTION EACH	SEDIMENT BASINS EACH	STONE RIPRAP, CLASS A4 SQ YD	FILTER FABRIC FOR USE WITH RIPRAP SQ YD
IL 173																	
229+50.00	LT&RT											2					
230+00.00	LT&RT											2					
230+50.00	LT&RT											2					
231+00.00	LT											1					
231+10.00	LT&RT											2					
NW INFIELD				23.75	15	1	2137.5	2137.5	2137.5	23.75					1		
I-90																	
411+50.00	87.0' LT															L77	L77
412+00.00	92.5' LT															L77	L77
414+00.00	100.0' LT															L77	L77
416+00.00	104.0' LT															L77	L77
418+00.00	110.8' LT															L77	L77
420+00.00	117.2' LT															L77	L77
421+00.00	RT			0.25			22.5	22.5	22.5	0.25	92			1			
421+00.00	120.0' LT															79.77	79.77
422+00.00	121.0' LT															L77	L77
424+00.00	120.0' LT															L77	L77
426+00.00	113.0' LT															L77	L77
428+00.00	101.0' LT															L77	L77
429+50.00	LT	431+00.00	LT													201.8	201.8
433+50.00	LT	435+00.00	LT													202.1	202.1
436+00.00	101.0' LT															L77	L77
438+00.00	102.5' LT															L77	L77
440+00.00	100.9' LT															L77	L77
442+00.00	101.0' RT															L77	L77
446+00.00	115.0' LT															L77	L77
447+00.00	112.5' LT															L77	L77
449+00.00	117.8' LT															L77	L77
450+00.00	LT															L77	L77
453+00.00	RT															L77	L77
453+00.00	118.0' LT															55.6	55.6
453+50.00	118.3' LT															L77	L77
458+00.00	LT	464+00.00	LT	1.00			90	90	90	1.00							
459+00.00	105.4' RT															L77	L77
472+60.00	127.27' RT															36.1	36.1
473+00.00	117.0' RT															L77	L77
474+54.00	LT	476+53.00	LT													267	267
474+98.00	95.0' LT															39	39
475+00.00	RT															L77	L77
475+50.00	RT	479+50.00	RT													533	533
481+00.00	RT															L77	L77
482+00.00	RT															L77	L77
RAMP A																	
800+00.00	RT	832+00.00	RT	6.50			585	585	585	6.50	2.87						
800+00.00	RT	800+00.00	RT														
800+00.00	RT																
800+10.00	RT																
800+20.00	RT																
802+00.00	RT																
804+00.00	RT																
805+00.00	RT																
807+00.00	RT																
808+40.00	LT	832+00.00	LT	4.00			360	360	360	4.00							
808+50.00	35.9' RT															L77	L77
809+00.00	RT															L77	L77
809+50.00	38.0' RT															L77	L77
811+00.00	RT																
812+00.00	LT																
812+00.00	38.1' RT															L77	L77
813+00.00	LT&RT											2					
814+00.00	LT											1					
814+00.00	39.1' RT														L77	L77	
815+00.00	LT																
816+00.00	LT&RT											2					
817+00.00	LT																
818+00.00	RT	832+00.00	RT								2.04						
818+00.00	LT																
820+00.00	RT																
SUB-TOTAL				35.5	15	1	3195	3195	3195	35.5	96.91	28	0	2	1	1463.93	1463.93

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES SCALE: VERT. N/A HORIZ. N/A DATE: SEPTEMBER 14, 2005	DRAWN BY: KRL CHECKED BY: PDS
NAME	DATE		