

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	47
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

## EROSION CONTROL SCHEDULE

STATION	OFF	STATION	OFF	MISC											RIPRAP		
				25000210	25000312	25000314	25000400	25000500	25000600	25100115	25100630	28000300	28000400	28000500	X0323260	28100107	28200100
				SEEDING, CLASS 2A	SEEDING, CLASS 4A	SEEDING, CLASS 4B	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	SEDIMENT BASINS	STONE RIPRAP, CLASS A4	FILTER FABRIC FOR USE WITH RIPRAP
				ACRE	ACRE	ACRE	POUND	POUND	POUND	ACRE	SQ. YD.	EACH	FOOT	EACH	EACH	SQ. YD.	SQ. YD.
<b>RAMP A</b>																	
822+00.00	LT&RT											2					
823+00.00	LT&RT											2					
823+50.00	LT&RT											2					
824+00.00	42.1' RT															68.9	68.9
825+00.00	LT&RT											2					
826+00.00	LT&RT											2					
828+00.00	LT&RT											2					
830+00.00	LT&RT											2					
<b>RAMP B</b>																	
5000+50.00	RT	5030+00.00	RT								4.56						
5001+50.00	LT	5019+00.00	LT								2.66						
5008+75.00	LT&RT												2				
5010+00.00	30.0' RT															L77	L77
5011+50.00	59.1' RT															L77	L77
5012+88.00	51.0' RT															53.3	53.3
5013+00.00	LT																
5013+50.00	LT	5018+00.00	LT	1.25			112.5	112.5	112.5	1.25							
5013+50.00	58.2' RT															L77	L77
5014+00.00	LT											1					
5015+00.00	59.0' RT															L77	L77
5016+00.00	LT											1					
5017+00.00	74.6' RT															L77	L77
5018+00.00	LT											1					
5018+59.60	96.1' RT															L77	L77
5019+00.00	96.1' RT															L77	L77
5031+60.00	RT	5063+82.85	RT	5.25			472.5	472.5	472.5	5.25							
5032+80.00	RT	5035+40.00	RT														
5033+00.00	RT	5036+00.00	RT										260				
5036+00.00	LT	5056+50.00	LT									0.35					
5036+50.00	RT											3.53					
5037+50.00	RT																
5038+50.00	RT																
5039+50.00	RT																
5040+50.00	RT																
5044+50.00	RT																
5045+50.00	RT																
5046+50.00	RT																
5047+50.00	RT																
5048+50.00	RT																
5049+50.00	RT																
5050+50.00	RT																
5051+50.00	RT																
5052+50.00	RT																
5053+50.00	RT																
5054+50.00	RT																
5055+50.00	RT																
5056+50.00	RT																
5057+50.00	RT																
5058+50.00	RT																
5059+50.00	RT																
5060+50.00	RT																
5061+50.00	RT																
5062+00.00	RT																
5062+50.00	RT																
5062+60.00	RT																
5062+70.00	RT																
5062+90.00	RT																
<b>RAMP C</b>																	
4000+50.00	RT	4017+00.00	RT								2.11						
4000+50.00	LT	4017+00.00	LT	3.50			315.0	315.0	315.0	3.50							
4000+50.00	RT	4041+63.40	RT	8.75			787.5	787.5	787.5	8.75							
4000+55.00	LT	4015+30.00	LT								2.54						
4002+50.00	RT																
4003+00.00	LT&RT																
4003+20.00	47.4' LT											2					
4003+50.00	LT&RT															L77	L77
4004+00.00	LT&RT											2					
4004+50.00	RT																
4005+00.00	LT	4010+00.00	LT											190			
<b>SUB-TOTAL</b>				18.75	0	0	1687.5	1687.5	1687.5	18.75	15.75	53	450	3	0	136.36	136.36

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"><b>SCHEDULE OF QUANTITIES</b></p> <p>SCALE: VERT. N/A      DRAWN BY KRL          HORIZ. N/A            CHECKED BY PDS          DATE: SEPTEMBER 14, 2005</p>