

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	57
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

MISCELLANEOUS SCHEDULE

STATION	OFF	STATION	OFF	SURVEY		REMOVAL		RUMBLE STRIP		FENCE				
				66700205 PERMANENT SURVEY MARKERS, TYPE I EACH	66700305 PERMANENT SURVEY MARKERS, TYPE II EACH	Z0049300 REFERENCING LAND SECTION MARKERS EACH	Z0023900 FILLING EXISTING WELLS EACH	Z0007550 BUILDING REMOVAL EACH	*2001365 SHOULDER RUMBLE STRIP REMOVAL SQ YD	64200105 SHOULDER RUMBLE STRIP FOOT	20101000 TEMPORARY FENCE, 6' FOOT	66400305 CHAIN LINK FENCE, 6' FOOT	66501200 WOVEN WIRE GATES, 4' X 8' DOUBLE EACH	66502405 WOVEN WIRE FENCE REMOVAL AND REPLACEMENT FOOT
IL 173														
142+32.87	85' RT	153+22.74	85' RT								1091			1091
142+50.00					1									
144+25.00	108' LT							1						
153+22.74	83' RT	156+00.00	122' RT								278			278
156+00.00	122' RT	156+99.85	135' RT								101			101
156+99.85	135' RT	158+99.85	135' RT								200			200
161+99.85	115' RT	165+99.85	115' RT								400			400
165+99.85	115' RT	167+99.85	85' RT								202			202
167+99.85	85' RT	170+00.00	85' RT								200			200
170+00.00	85' RT	182+78.39	85' RT								1278			1278
182+78.39	85' RT	182+94.40	85' RT								16		1	
182+94.40	85' RT	184+00.00	85' RT								106			106
183+16.00	60' LT													
183+21.41	65' LT													
183+41.00	121' LT													
183+58.00	86' LT													
183+78.10	65' LT													
184+00.00	85' RT	190+01.00	85' RT								601			601
231+00.00					1									
IL 173						3								
I-90														
389+00.00		409+96.78	SB OUTSIDE								2096.78			
389+00.00		410+93.02	SB OUTSIDE					974.7						
389+00.00		421+85.50	NB OUTSIDE								3285.5			
389+00.00		441+50.99	NB INSIDE								5250.99			
389+00.00		441+70.28	SB INSIDE								5270.28			
389+00.00		500+78.90	SB INSIDE											
429+02.50		441+50.99	NB OUTSIDE					4968.4						
445+86.70		457+41.43	NB OUTSIDE								1248.49			
445+86.70		500+78.90	NB INSIDE								1154.73			
446+10.17		500+78.90	SB INSIDE								5492.2			
454+84.43		468+14.21	SB OUTSIDE								5468.73			
476+52.26		500+78.90	SB OUTSIDE								1329.78			
476+58.66		500+78.90	SB OUTSIDE					1078.5			2420.24			
482+57.91		500+78.90	NB OUTSIDE								1820.99			
NB BRIDGE					1									
SB BRIDGE					1									
RAMP A														
800+48.52	96.11' RT	831+73.75	127.35' RT								3079			
RAMP C														
4000+99.59	107.70' RT	4016+99.87	74.56' RT								1658			
4030+91.45	86.29' RT	4040+89.61	117.61' RT								1142			
RAMP D														
1306+00.13	72.62' RT	1320+53.95	237.34' RT								1466			
TOTAL				2	2	3	2	4	7022	34839	4473	7345	1	4457

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES SCALE: VERT. N/A HORIZ. N/A DATE: SEPTEMBER 14, 2005	DRAWN BY KRL CHECKED BY PDS
NAME	DATE		