

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	I29 K	WINNEBAGO	585	154
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
190/ IL 173				

TRAFFIC SIGNAL TABULATION

CODE NUMBER	ITEM	UNIT	ROCK CUT STATE PARK ENTRANCE	SB RAMPS	NB RAMPS	TOTAL
80400105	SERVICE INSTALLATION, SPECIAL	EACH	1	1	1	3
81400400	CONCRETE HANDHOLE	EACH	5	5	4	14
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1	1	1	3
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1594	770	802	3166
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 250 WATT	EACH	4	3	1	8
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1	1	1	3
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1	1	3
87301245	ELECTRIC CABLE SIGNAL No. 14, 5C	FOOT	2050	3346	3147	8543
87301255	ELECTRIC CABLE SIGNAL No. 14, 7C	FOOT	1140	584	1451	3175
87301815	ELECTRIC CABLE IN CONDUIT SERVICE #6 3C	FOOT	51	63	24	138
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14FT	EACH	2	3	0	5
87502460	TRAFFIC SIGNAL POST, GALVANIZED STEEL 12FT	EACH	0	2	3	5
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT	EACH	0	1	1	1
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT	EACH	0	1	1	2
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT	EACH	0	0	1	1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT	EACH	1	0	0	1
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT	EACH	3	1	0	4

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
 HORIZ. _____

DATE _____

DRAWN BY _____
 CHECKED BY _____