

TRAFFIC SIGNAL TABULATION CONT.

CONTRACT NO. 64594				
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	I29 K	WINNEBAGO	585	155
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
190/ IL 173				

CODE NUMBER	ITEM	UNIT	STATE PARK ENTRANCE	SB RAMP	NB RAMP	TOTAL
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6	15	18	39
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5	3.5	3.5	10
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	58	39	27	124
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	8	8	7	23
X0324886	CONDUIT INSTALLED 1 1/4", NON-METALLIC	FOOT	51	33	24	108
X0324887	CONDUIT INSTALLED 2 1/2", NON-METALLIC	FOOT	155	199	104	458
X0324888	CONDUIT INSTALLED 4", NON-METALLIC	FOOT	422	335	536	1293
X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	1	1	1	3
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, No. 6 IC (GREEN)	FOOT	625	525	565	1715
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, I-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7	7	6	19
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, I-FACE, 3-SECTION, BRACKET MOUNT	EACH	1	4	5	10
X8801395	SIGNAL HEAD, POLYCARBONATE, LED, I-FACE, 5-SECTION, BRACKET MOUNT	EACH	2	2	0	4
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, I-FACE, 5-SECTION, MAST-ARM MOUNT	EACH	1	1	1	3
X8801415	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, -3-SECTION, BRACKET MOUNT	EACH	0	0	2	2
X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, I-3-SECTION, I-5-SECTION, BRACKET MOUNT	EACH	1	0	0	1
X8801447	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, -5-SECTION, BRACKET MOUNT	EACH	0	1	0	1
X0323712	RADIO INTERCONNECT SYSTEM COMPLETE, MASTER	EACH	0	1	0	1
X0300737	RADIO TRANSCEIVER	EACH	1	0	1	2
XX003163	EMERGENCY VEHICLE PRIORITY SYSTEM	EACH	1	1	1	3

PLOT DATE = *DATE*
 FILE NAME = *FILEL*
 USER NAME = *USER*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY

TRAFFIC SIGNALS