CONTRACT NO. 64594

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129K	WINNEBAGO	585	306
STA.	STA. TO STA.			

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 78"

Use 2 layers of welded wire fabric

in back face of wingwalls.

RAMP C - STA. 4009 + 69.6 RT. TO STA. 4010 + 57.1 LT.

GENERAL NOTES

Build tops of headwalls parallel to grade line.

When lapping sheets of welded wire fabric, the overlap measured between the outermost cross wires of each fabric sheet shall not be less than 8".

All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).

culvert

Welded wire fabric (†yp.) 6"x6" - W4.0xW4.0

Welded wire fabric, reinforcement bars, and all materials required to construct the CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 78" as shown herein shall be included in the contract cost per EACH.

