

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	28-SO-M	JO DAVIESS	27	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

20101700 SUPPLEMENTAL WATERING

LOCATION	UNITS	REMARKS
10+00.00 TO 15+00.00	18.0	ENTRANCE ROAD
15+00.00 TO 18+39.54	5.5	ENTRANCE ROAD
20+00.00 TO 22+00.00	3.2	GORE AREA
22+00.00 TO 24+00.00	2.4	CIRCULATORY ROADWAY
24+00.00 TO 27+50.00	33.3	PARKING AREA
27+50.00 TO 34+00.00	21.2	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	4.1	GORE AREA
REPAIR / REPLACE SIDEWALK PERIMETER	1.9	
EXISTING SIDEWALK PERIMETER	2.6	
30+40.00 RT	0.8	DUMPSTER PAD
TOTAL		93

25200100 SODDING

LOCATION	SQ. YD	REMARKS
10+00.00 TO 15+00.00	400.0	ENTRANCE ROAD
15+00.00 TO 18+39.54	121.5	ENTRANCE ROAD
20+00.00 TO 22+00.00	70.8	GORE AREA
22+00.00 TO 24+00.00	54.2	CIRCULATORY ROADWAY
24+00.00 TO 27+50.00	740.3	PARKING AREA
27+50.00 TO 34+00.00	470.8	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	91.7	GORE AREA
REPAIR / REPLACE SIDEWALK PERIMETER	42.0	
EXISTING SIDEWALK PERIMETER	57.6	
30+40.00 RT	20.0	DUMPSTER PAD
TOTAL		2069

35102400 AGGREGATE BASE COURSE, TYPE B, 12"

LOCATION	SQ. YD	REMARKS
24+09.00 TO 27+50.00 RT	557.1	AT PARKING RIGHT SIDE
25+50.00 TO 27+68.00 LT	624.9	AT PARKING LEFT SIDE
29+40.00 TO 35+08.00 LT	339.8	AT WIDENING LEFT SIDE
30+31.00 TO 30+45.00 RT	10.7	AT DUMPSTER PAD
TOTAL		1532

40500100 BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	TON	REMARKS
10+00.00 TO 15+00.00	0.30	ENTRANCE ROAD
15+00.00 TO 22+00.00	0.28	ENTRANCE ROAD
22+00.00 TO 24+00.00	0.05	GORE
24+00.00 TO 27+50.00	0.35	PARKING AREA
27+50.00 TO 34+00.00	0.26	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	0.06	RETURN GORE AREA
TOTAL		1.3

40500300 BITUMINOUS MIX COMPLETE

LOCATION	TON	REMARKS
10+00.00 TO 15+00.00	249.6	ENTRANCE ROAD
15+00.00 TO 22+00.00	238.2	ENTRANCE ROAD
22+00.00 TO 24+00.00	42.0	GORE
24+00.00 TO 27+50.00	292.4	PARKING AREA
27+50.00 TO 34+00.00	222.2	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	46.6	RETURN GORE AREA
TOTAL		1091

40600980 BITUMINOUS SURFACE REMOVAL BUTT JOINT

LOCATION	SQ. YD	REMARKS
10+00.00 TO 10+30.00 LT TO RT	221.1	OVERLOOK ENTRANCE
15+46.00 TO 24+09.00 RT	191.8	LOWER PARKING AREA
23+33.00 TO 25+50.00 LT	48.2	LOWER PARKING AREA
TOTAL		461

42400200 PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH

LOCATION	SQ. FT	REMARKS
25+50.00 TO 27+50.00 LT	1500.0	ALONG PARKING AREA
26+10.00 TO 26+40.00 LT	339.0	AT SIDEWALK REPLACEMENT AREA
26+90.00 TO 27+10.00 LT	90.0	AT SIDEWALK EXTENSION AREA
24+43.00 TO 24+50.00 LT	50.6	AT SIDEWALK REPAIR AREAS
24+75.00 TO 24+82.00 LT	49.8	AT SIDEWALK REPAIR AREAS
24+95.00 TO 25+25.00 LT	276.1	AT SIDEWALK REPAIR AREAS
25+10.00 TO 25+22.00 LT	72.0	AT SIDEWALK REPAIR AREAS
25+30.00 TO 25+39.00 LT	51.6	AT SIDEWALK REPAIR AREAS
25+40.00 TO 25+50.00 LT	48.5	AT SIDEWALK REPAIR AREAS
25+65.00 TO 25+75.00 LT	54.0	AT SIDEWALK REPAIR AREAS
25+76.00 TO 25+86.00 LT	61.3	AT SIDEWALK REPAIR AREAS
26+33.00 TO 26+50.00 LT	117.3	AT SIDEWALK REPAIR AREAS
TOTAL		2710

EARTHWORK SCHEDULE

LOCATION		20200100 EARTH EXCAVATION (CUT)	20200500 EARTH EXCAVATION (WIDENING)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
FROM	TO	CU YD	CU YD	CU YD	CU YD	CU YD
ENTRANCE ROAD						
10+00.00	15+00.00	0.0	0.0	0.0	6.5	-6.5
15+00.00	18+39.54	0.0	0.0	0.0	3.0	-3.0
20+00.00	22+00.00	0.0	0.0	0.0	1.9	-1.9
22+00.00	24+00.00	0.0	0.0	0.0	1.6	-1.6
PARKING AREA						
24+00.00	27+50.00	15.7	149.5	123.9	317.2	-193.3
CIRCULATORY ROADWAY						
27+50.00	34+00.00	2.1	180.1	136.7	12.2	124.4
34+00.00	36+00.00	0	54.5	40.9	1.9	39.1
TOTALS		18	384	301	344	-43
		20200100 EARTH EXCAVATION 18 CU YD	20200500 EARTH EX (WIDENING) 384 CU YD			20400800 FURNISHED EXCAVATION 43 CU YD

44000600 SIDEWALK REMOVAL

LOCATION	SQ. FT	REMARKS
25+50.00 TO 25+60.00 LT	101.7	ALONG PARKING AREA
26+10.00 TO 26+40.00 LT	225.0	AT SIDEWALK REPLACEMENT AREA
24+43.00 TO 24+50.00 LT	50.6	AT SIDEWALK REPAIR AREAS
24+75.00 TO 24+82.00 LT	49.8	AT SIDEWALK REPAIR AREAS
24+95.00 TO 25+25.00 LT	276.1	AT SIDEWALK REPAIR AREAS
25+10.00 TO 25+22.00 LT	72.0	AT SIDEWALK REPAIR AREAS
25+30.00 TO 25+39.00 LT	51.6	AT SIDEWALK REPAIR AREAS
25+40.00 TO 25+50.00 LT	48.5	AT SIDEWALK REPAIR AREAS
25+65.00 TO 25+75.00 LT	54.0	AT SIDEWALK REPAIR AREAS
25+76.00 TO 25+86.00 LT	61.3	AT SIDEWALK REPAIR AREAS
26+33.00 TO 26+50.00 LT	117.3	AT SIDEWALK REPAIR AREAS
TOTAL		1108

60600605 CONCRETE CURB, TYPE B

LOCATION	FEET	REMARKS
25+50.00 TO 27+70.00 LT	245.0	ALONG PARKING AREA
TOTAL		245

60603300 GUTTER OUTLET

LOCATION	EACH	REMARKS
27+50.00 TO 27+80.00 RT	1	AT BUS PARKING AREA
TOTAL		1

60607400 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24

LOCATION	FEET	REMARKS
24+09.00 TO 27+54.00 RT	345.0	AT BUS PARKING AREA
TOTAL		345

67100100 MOBILIZATION

LOCATION	L. SUM	REMARKS
ENTIRE JOBSITE	1	
TOTAL		1

72000100 SIGN PANEL - TYPE 1

LOCATION	SQ. FT	REMARKS
26+00.00 TO 26+15.00 TO 33' LT	2.0	PER D2 CAD STD 44.2
26+15.00 TO 33' LT	2.0	PER D2 CAD STD 44.2
TOTAL		4

PLOT DATE = 8/12/05
FILE NAME = 815118
PLOT SCALE = 1"=40'
REFERENCE = BREF

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

REVISIONS	
NAME	DATE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY SAM
CHECKED BY RJA