

SUMMARY OF QUANTITIES

PROJECT NO. 599	SECTION •	COUNTY ROCK ISLAND	TOTAL SHEETS 90	SHEET NO. 4
STA.		TO STA.		
EXISTING CONDITIONS: • 42 MET. BR. (BR-2M) • 42 FT. 1				
				CONTRACT 64641

← 80% FED 20% STATE →

CODE NUMBER	ITEM	UNITS	TOTAL	1000-2A	SN 081-1008 X028-2A	Y060 VILLAGE OF ANDALUSIA 100% Village	SN 081-1008 X028-2A 80% FED 20% STATE	SN 081-0076 SFTY-2A 80% FED 20% STATE
* A2006514 B2003516 20100110 B2005316 20200100	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1- 3/4" CALIPER, BALLED AND BURLAPPED TREE, MALUS HARVEST GOLD (HARVEST GOLD CRABAPPLE), 2" CALIPER, TREE FORM, BALLED & BURLAPPED TREE REMOVAL (6 TO 15 UNITS DIAMETER) TREE, MALUS ZUNI CALOCARPA (REDBUD ZUNI CRABAPPLE), 2" CALIPER, TREE FORM, BALLED & BURLAPPED EARTH EXCAVATION	EACH EACH UNIT EACH CU YD	25 4 300 4 3,694	25 4 300 4 3,650			44	
20300100	CHANNEL EXCAVATION	CU YD	192	192			316	
20400800	FURNISHED EXCAVATION	CU YD	3,004	2,688				
20800150	TRENCH BACKFILL	CU YD	560	560			360	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8,068	7,708				
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	50	50			0.25	
25000200	SEEDING, CLASS 2	ACRE	0.25					
25000310	SEEDING, CLASS 4	ACRE	1.75	1.75				
25000750	MOWING	ACRE	1.75	1.75				
25000910	SEEDING, CLASS 1 (MODIFIED)	ACRE	1.00	1.00				
25001830	SEEDING, CLASS 6 (MODIFIED)	ACRE	0.75	0.75				
25100115	MULCH, METHOD 2	ACRE	10.50	10.50				
25100630	EROSION CONTROL BLANKET	SQ YD	1,084	1,084				
25200110 28000250	SEEDING, SALT TOLERANT TEMPORARY EROSION CONTROL SEEDING	SQ YD POUND	776 720	776 700			20	
28000300	TEMPORARY DITCH CHECKS	EACH	17	17			855	
28000400	PERIMETER EROSION BARRIER	FOOT	2,891	2,036				
28000500	INLET AND PIPE PROTECTION	EACH	10	10				
28100109	STONE RIPRAP, CLASS A5	SQ YD	273	273				
28200400	FILTER FABRIC	SQ YD	273	273				
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	SQ YD	407	407				
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ YD	2,825	2,825				
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	100	100				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,265	1,265				
40600100	BITUMINOUS CONCRETE SURFACE COURSE, MIXTURE C, CLASS I, TYPE 1 N50	TON	230	230				
40600990	TEMPORARY RAMP	SQ YD	36	36			115	
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	115					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1,059	1,059				
44000100	PAVEMENT REMOVAL	SQ YD	2,744	2,744				
44000400	GUTTER REMOVAL	FOOT	305	305				
44000075	BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE	SQ YD	236	0			236	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,692	1,692				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	515	235			280	
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	620	620				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1			
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	173		173			
50300225	CONCRETE STRUCTURES	CU YD	110		110			
50300260	BRIDGE DECK GROOVING	SQ YD	257				257	
50300265	SEAL COAT CONCRETE	CU YD	7		7			
50300300	PROTECTIVE COAT	SQ YD	266				266	
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	327					327
50800105	REINFORCEMENT BARS	POUND	56,970		56,970			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,530				3,530	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	109				109	
51500100	NAME PLATES	EACH	3		2		1	
54003000	CONCRETE BOX CULVERTS	CU YD	271.9		271.9			

NON-PARTICIPATING
* SPECIALTY ITEM
+ SFTY-3N ITEM

05/09/2005
DATE-TIME:
• 00:00:00
• 00:00:00
• 00:00:00