

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	26VBR-1	DEKALB	39	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X180-2A 80% FED / 20% STATE	SFTY - 3N 80% FED / 20% STATE
20200100	EARTH EXCAVATION	CU YD	216	216	
20400800	FURNISHED EXCAVATION	CU YD	55	55	
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	225	225	
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	10	10	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	412	412	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50300260	BRIDGE DECK GROOVING	SQ YD	685	685	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	716	716	
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	591	591	
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	6648	6648	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9390	9390	
50901005	STEEL BIRDEGE RAIL, TYPE SM	FOOT	278	278	
51500100	NAME PLATES	EACH	1	1	
59000100	EPOXY CRACK SEALING	FOOT	68	68	
61100605	MISCELLANEOUS CONCRETE	CU YD	2.4	2.4	
• 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	150	150	
• 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
63301210	REMOVE AND RE - ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	765	765	
63500105	DELINEATORS	EACH	3	3	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	690	690	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	570	570	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2520	2520	
• 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	387	387	
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	58	58	
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	58	58	
X0712400	TEMPORARY PAVEMENT	SQ YD	174	174	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	25	25	
X6330103	REMOVE AND RE - ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	3	3	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	96	96	
Z0002600	BAR SPLICERS	EACH	149	149	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2
① 50300300	PROTECTIVE COAT	SQ YD	742	742	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
*SPECIALTY ITEMS					

PLOT DATE = Tue Aug 30 14:28:07 2005
 FILE NAME = c:\projects\26vbr-1\886485.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 USER NAME = mgj111

① REVISED
 11-01-05