CONTRACT NO. 64B10

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5862	2BR-1	HENRY	26	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

URBAN
X080-2A
80 % FED
20 % STATE

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	127
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	770
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40
25100630	EROSION CONTROL BLANKET	SQ YD	770
28000400	PERIMETER EROSION BARRIER	FOOT	725
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	107
48101200	AGGREGATE SHOULDERS, TYPE B	TON	280
50101500	REMOVAL OF EXISTING SUPERSTRUCTURE	EACH	1
50102400	CONCRETE REMOVAL	CU YD	9.2
50300260	BRIDGE DECK GROOVING	SQ YD	721
50300300	PROTECTIVE COAT	SQ YD	914
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.7
5030 1245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	30
50301200	CONCRETE WEARING SURFACE	SQ. YD.	744
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ. FT.	7046
50800205	REINFOREMENT BARS, EPOXY COATED	POUND	10170
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	474
51500100	NAME PLATES	EACH	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	187.5
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4

* SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Fri Sep 02 14:39:49 2005
FILE NAME = c:\pw_work\pw207285\db72285csvr.dgn
PLOT SCALE = 50.000000 ' / IN.
USER NAME = meglilj