

F.A.W. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5862	2BR-1	HENRY	26	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES POPPY GARDEN

20200100	EARTH EXCAVATION				
	CU YD	LOCATION			
	52	6 + 66 -	8 + 3		
	75	10 + 12 -	12 + 11	LT & RT	
	127	TOTAL			
28000400	PERIMETER EROSION BARRIER				
	FOOT	LOCATION			
	50	7 + 58.37 -	8 + 0.97	RT	
	178	6 + 65.91 -	8 + 3.39	LT	
	270	10 + 12.41 -	12 + 10.59	LT	
	227	10 + 12.35 -	11 + 81.32	RT	
	725	TOTAL			
44000007	BITUMINOUS CONCRETE SURFACE REMOVAL 2"				
	SQ YD	LOCATION			
	53	7 + 80.87 -	8 + 0.87		
	54	10 + 14.76 -	10 + 34.92		
	107	TOTAL			
48101200	AGGREGATE SHOULDERS, TYPE B				
	ION	LOCATION			
	52	6 + 65.91 -	8 + 3.4	LT	
	15	7 + 59.38 -	8 + 0.97	RT	
	68	10 + 11.95 -	12 + 10.59	LT	
	65	10 + 12.36 -	11 + 81.32	RT	
	80	Good neighbor policy			
	280	TOTAL			
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A				
	FOOT	LOCATION			
	37.5	7 + 31.87 -	7 + 69.57	LT	
	50	10 + 46.11 -	10 + 96.26	RT	
	100	10 + 45.7 -	11 + 46.46	LT	
	187.5	TOTAL			
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A				
	EACH	LOCATION			
	1	7 + 69.67 -	8 + 3.45	RT	
	1	7 + 69.57 -	8 + 3.4	LT	
	1	10 + 12.36 -	10 + 46.11	RT	
	1	10 + 11.95 -	10 + 45.7	LT	
	4	TOTAL			
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)				
	EACH	LOCATION			
	1	7 + 19.67 -	7 + 69.67	RT	
	1	TOTAL			
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)				
	EACH	LOCATION			
	1	6 + 81.88 -	7 + 31.87	LT	
	1	11 + 46.46 -	11 + 96.54	LT	
	1	10 + 96.26 -	11 + 46.32	RT	
	3	TOTAL			

PLOT DATE = Fri Sep 02 14:33:49 2005
 FILE NAME = c:\pwork\jens\207265\087205.dgn
 USER = mag11j

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY