

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5862	2BR-1	HENRY	26	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

POPPY GARDEN

63200310

GUARDRAIL REMOVAL

FOOT	LOCATION				
90	7+ 13.85	-	8+ 3.16	LT	
53	7+ 56.97	-	8+ 2.95	RT	
91	10+ 11.95	-	11+ 2.12	LT	
91	10+ 12.08	-	11+ 2.18	RT	
325	TOTAL				

63500105

DELINEATORS

EACH	LOCATION				
1	6+ 81.88	LT			
1	7+ 19.67	RT			
1	11+ 46.32	RT			
1	11+ 96.54	LT			
4	TOTAL				

78001110

PAINT PAVEMENT MARKING LINE 4"

FOOT	LOCATION				
260	6+ 81.88 - 11+ 96.54				YELLOW SKIP DASH - 2 COATS
1028	6+ 81.88 - 11+ 96.54				YELLOW CENTER LINE - 2 COATS
1028	6+ 81.88 - 11+ 96.54	LT			WHITE EDGELINES - 2 COATS
1028	6+ 81.88 - 11+ 96.54	RT			WHITE EDGELINES - 2 COATS
3344	TOTAL				

78200410

GUARDRAIL MARKERS, TYPE A

EACH	LOCATION				
4	6+ 81.88	-	8+ 3.4	LT	
3	7+ 19.67	-	8+ 3.45	RT	
5	10+ 12.36	-	11+ 46.32	RT	
7	10+ 11.95	-	11+ 96.54	LT	
19	TOTAL				

78201000

TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION				
1	8+ 3.4	LT			
1	8+ 3.45	RT			
1	10+ 12.36	RT			
1	10+ 11.95	LT			
4	TOTAL				

28000250

TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION				
40	6+ 65.91 - 12+ 10.59	LT & RT			
40	TOTAL				

X4066414

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50

TON	LOCATION				
10	7+ 81.08 - 8+ 1.08				
10	10+ 14.76 - 10+ 34.76				
50	Good neighbor policy				
70	TOTAL				

25100630

EROSION CONTROL BLANKET

SQ. YD	LOCATION				
6.9	7+ 58.37 - 8+ 0.97	RT			
114.2	6+ 65.91 - 8+ 3.39	LT			
226.1	10+ 12.41 - 12+ 10.59	LT			
422.2	10+ 12.35 - 11+ 81.32	RT			
770	TOTAL				

21101615

TOPSOIL FURNISH AND PLACE 4"

SQ. YD	LOCATION				
6.9	7+ 58.37 - 8+ 0.97	RT			
114.2	6+ 65.91 - 8+ 3.39	LT			
226.1	10+ 12.41 - 12+ 10.59	LT			
422.2	10+ 12.35 - 11+ 81.32	RT			
770	TOTAL				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. DATE HORIZ. DRAWN BY: CHECKED BY: