

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 627	1 BR	LaSALLE	46	3
ILLINOIS				

CONTRACT NO. 66364

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	% FED. % STATE	
				% FED. % STATE	% FED. % STATE
				CONSTRUCTION TYPE	
				ROADWAY 80% FED. 20% ST. X071-2A	STRUCTURE 80% FED. 20% ST. X071-2A
20101000	TEMPORARY FENCE	FOOT	327	327	
20200100	EARTH EXCAVATION	CU YD	145	145	
20300100	CHANNEL EXCAVATION	CU YD	390	390	
20400800	FURNISHED EXCAVATION	CU YD	153	153	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	120		120
25000200	SEEDING, CLASS 2	ACRE	0.18	0.18	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	18	18	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18	
25100105	MULCH METHOD 1	ACRE	0.18	0.18	
25100115	MULCH METHOD 2	ACRE	0.18	0.18	
28000250	TEMPORARY EROSION CONTROL SEEDINGS	POUND	18	18	
28000400	PERIMETER EROSION BARRIER	FOOT	1268	1268	
28100109	STONE RIPRAP, CLASS A5	SQ YD	385		385
28200200	FILTER FABRIC	SQ YD	385		385
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	213	213	
40600300	AGGREGATE (PRIME COAT)	TON	6	6	
40600985	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	375	375	
40600990	TEMPORARY RAMP	SQ YD	130	130	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	2	2	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	229	229	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44	44	
44000100	PAVEMENT REMOVAL	SQ YD	301	301	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	124	124	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	599	599	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	285		285
50300100	FLOOR DRAINS	EACH	4		4
50300225	CONCRETE STRUCTURES	CU YD	65.6		65.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	104.8		104.8
50300260	BRIDGE DECK GROOVING	SQ YD	294		294
50300300	PROTECTIVE COAT	SQ YD	360		360

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	% FED. % STATE	
				% FED. % STATE	% FED. % STATE
				CONSTRUCTION TYPE	
				ROADWAY 80% FED. 20% ST. X071-2A	STRUCTURE 80% FED. 20% ST. X071-2A
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	1296		1296
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	30190		30190
51201400	FURNISHING STEEL PILES HP10X42	FOOT	216		216
51201600	FURNISHING STEEL PILES HP12X53	FOOT	108		108
51500100	NAME PLATES	EACH	1		1
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	312.5	312.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	410	410	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	256	256	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2990	2990	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	190	190	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	48	48	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	700	700	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	650	650	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1215	1215	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	560	560	

\* SPECIALTY ITEMS

**SUMMARY OF QUANTITIES**  
 IL. RTE. 71 OVER UNNAMED STREAM  
 F.A.P. RTE. 627 - SECTION 1BR  
 LaSALLE COUNTY  
 STA. 14+08.00  
 STR. NO. 050-0244

4440 ASH GROVE SPRINGFIELD, IL. 62707 (217) 793-8600 oasinc@famvid.com	<b>OZYURT AND STONE, INC.</b> CONSULTING ENGINEERS	JOB NO.: 0306.4 FILE: SUM001.DGN DATE: 07-20-05
---	---	---