

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 627	1 BR	LaSALLE	46	6

ILLINOIS CONTRACT NO. 66364

### PAVEMENT MARKING SCHEDULE

LOCATION	SHORT TERM		TEMPORARY			PERMANENT				RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	RAISED REFLECTIVE PAVEMENT MARKER		
	YELLOW	WHITE	YELLOW 4"	WHITE 4"	YELLOW 6"	PAINT		THERMOPLASTIC	PREFORMED, PLASTIC TYPE B				
						YELLOW 4"	WHITE 4"	YELLOW 6"	WHITE 4"			YELLOW 4" EACH	YELLOW 6" EACH
RT. STA. 10+81 TO STA. 17+63 (STAGE I)													
LT. STA. 11+34 TO STA. 12+00 (STAGE II)													
LT. STA. 16+83 TO STA. 17+62 (STAGE II)													
STA. 10+52.66 TO STA. 18+00	144		1495		190								
LT. & RT. STA. 10+52.66 TO STA. 18+00		112		1495									
STA. 13+36.67 TO STA. 14+76.70						280		40					
LT. & RT. STA. 13+36.67 TO STA. 14+76.70							280						
LT. & RT. STA. 10+52.66 TO STA. 13+36.67									568				
LT. & RT. STA. 14+76.70 TO STA. 18+00									647				
STA. 10+52.66 TO STA. 13+36.67										568	70		
STA. 14+76.70 TO STA. 18+00										647	80		
STA. 10+90 TO STA. 13+30												4	
STA. 14+90 TO STA. 17+30												4	
STA. 14+10											1		
TOTALS	144	112	1495	1495	190	280	280	40	1215	1215	150	1	8

TOTALS

144

112

1495

1495

190

280

280

40

1215

1215

150

1

8

### GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 6	STEEL PLATE BEAM GUARDRAIL, TYPE A	TERMINAL MARKER-DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B
	FOOT	EACH	EACH	FOOT	EACH	EACH	EACH
S.N. 050-0244							
SOUTHWEST QUADRANT	102	1	1	125	1	2	
NORTHWEST QUADRANT	102	1	1	37.5	1	1	
NORTHEAST QUADRANT	103	1	1	75	1	2	
SOUTHEAST QUADRANT	103	1	1	75	1	2	
WESTBOUND PARAPET							2
EASTBOUND PARAPET							2
TOTALS	410	4	4	312.5	4	7	4

### EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	ESTIMATED SUITABLE STRUCTURE EXCAVATION	SUITABLE STRUCT. EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FOR INFORMATION ONLY)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)**
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
STA. 10+52.66 TO STA. 18+00	145	109			360	-251
WEST ABUTMENT			65	49	0	+49
EAST ABUTMENT			65	49	0	+49
TOTALS	145	109	130	98	360	-153

\*\*FURNISHED EXCAVATION

### TEMPORARY MAINTENANCE OF TRAFFIC SCHEDULE

LOCATION	TRAFFIC CONTROL & PROTECTION STD. 701321	TRAFFIC CONTROL & PROTECTION STD. 701306	TRAFFIC CONTROL & PROTECTION STD. 701326	TEMPORARY BRIDGE TRAFFIC SIGNALS	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	TEMPORARY RUMBLE STRIP	TEMPORARY BITUMINOUS BASE COURSE 8"
	EACH	L SUM	L SUM	EACH	SQ FT	FOOT	FOOT	EACH	EACH	EACH	SQ YD
STAGE I CONSTRUCTION	0.5	0.5	0.5	1		700		2		6	520
STAGE II CONSTRUCTION	0.5	0.5	0.5		48		650		2		
TOTALS	1	1	1	1	48	700	650	2	2	6	520

### SCHEDULES

IL. RTE. 71 OVER UNNAMED STREAM  
 F.A.P. RTE. 627 - SECTION 1BR  
 LaSALLE COUNTY  
 STA. 14+08.00  
 STR. NO. 050-0244

4440 ASH GROVE  
 SPRINGFIELD, IL 62707  
 (217) 793-8600  
 oasinc@tamvid.com

**OZYURT AND STONE, INC.**  
 CONSULTING ENGINEERS

JOB NO.: 0306.4  
 FILE: SCHED02.DGN  
 DATE: 07-20-05