

CONTRACT NO. 66410

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
131T	109 BRN	KANKAKEE	58	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION	TYPE CODE
				ACRS ROADWAY 1000-1A	ACBRS BRIDGE X071-2A
20100500	TREE REMOVAL, ACRES	ACRE	0.26	0.26	
20200100	EARTH EXCAVATION	CU YD	816	816	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	125		125
25000300	SEEDING, CLASS 3	ACRE	0.74	0.74	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	68	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68	68	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	68	
25100115	MULCH, METHOD 2	ACRE	0.74	0.74	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	244	244	
28000300	TEMPORARY DITCH CHECKS	FACH	6	6	
28000400	PERIMETER EROSION BARRIER	FOOT	1142	1142	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100107	STONE RIPRAP, CLASS A4	SQ YD	960		960
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	1585	1585	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	639	639	
40600300	AGGREGATE (PRIME COAT)	TON	5	5	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	200	200	
40600990	TEMPORARY RAMP	SQ YD	42	42	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	214	214	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	42	42	
44000100	PAVEMENT REMOVAL	SQ YD	216	216	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	161	161	
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	166	166	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105200	REMOVE EXISTING CULVERTS	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	210		210
50300100	FLOOR DRAINS	EACH	12		12
50300225	CONCRETE STRUCTURES	CU YD	54		54
50300255	CONCRETE SUPERSTRUCTURE	CU YD	129		129
50300260	BRIDGE DECK GROOVING	SQ YD	319		319
50300300	PROTECTIVE COAT	SQ YD	402		402
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6		6
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	1206		1206
50800105	REINFORCEMENT BARS	POUND	2161		2161
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	34490		34490
51500100	NAME PLATES	EACH	1		1
54215550	METAL END SECTIONS 15"	EACH	2	2	
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	97	97	

• SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____