

F.A.S. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1317	109 BRN	KANKAKEE	58	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION ACRS		TYPE CODE ACBRS
				ROADWAY I000-1A	BRIDGE X071-2A	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	338	338		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	568	568		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	5	5		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	420	420		
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2750	2750		
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	343	343		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	47	47		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	27	27		
73000100	WOOD SIGN SUPPORT	FOOT	37.5	37.5		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2750	2750		
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	343	343		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		
* 78200405	GUARDRAIL MARKERS	EACH	9	9		
78200500	BARRIER WALL MARKERS	EACH	4	4		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10		
X3550600	BITUMINOUS BASE COURSE SUPERPAVE 9"	SQ YD	1468	1468		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	219	219		
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	2	2		
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	247	247		
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	LSUM	1	1		
* Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22		22	
Z0002000	FILTER FABRIC	SQ YD	1055		1055	
Z0002600	BAR SPLICERS	EACH	66		66	
* Z0008242	DRILLED SHAFT IN SOIL 42"	FOOT	45		45	
* Z0008336	DRILLED SHAFT IN ROCK 36"	FOOT	28		28	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE