

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	*	MACON	13	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* D5 ANNUAL PATCH 2006-5

SCHEDULE OF QUANTITIES

TABULATION OF CLASS A PAVEMENT PATCHING

MACON COUNTY NORTHBOUND
CLASS A PAVEMENT PATCH - 9 INCH

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	TYPE 1 44200525 (SQ. YD.)	TYPE 2 44200529 (SQ. YD.)	TYPE 3 44200533 (SQ. YD.)	TYPE 4 44200535 (SQ. YD.)	SAWCLTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	PATCH REINF 44213000 (SQ. YD.)
411+80.00		EMERY ROAD								
358+50.00		WISE ROAD								
358+30.00	RADIUS	4.50	15.00		7.5			69.0	0.0	7.5
358+05.00	RTL	4.50	50.00				25.0	209.0	0.0	25.0
337+66.00	NBDL	5.00	6.00	3.3				34.0	0.0	3.3
335+64.00	NBDL	6.00	12.00		8.0			60.0	0.0	8.0
335+64.00	*NBPL*	6.00	12.00		8.0			54.0	0.0	8.0
305+10.00		SCHELLABARGER								
298+72.00	NBDL	6.00	6.00	4.0				36.0	0.0	4.0
271+70.00	NBDL	6.00	12.00		8.0			60.0	0.0	8.0
271+70.00	*NBPL*	12.00	12.00			16.0		72.0	0.0	16.0
269+60.00	NBDL	6.00	12.00		8.0			60.0	0.0	8.0
269+60.00	*NBPL*	6.00	12.00		8.0			54.0	0.0	8.0
268+36.00	NBDL	10.00	12.00		13.3			68.0	0.0	13.3
PAGE TOTALS				7.3	60.8	16.0	25.0	776.0	0.0	109.1

CLASS A PAVEMENT PATCH - 9 INCH TOTALS	23.3	71.5	16.0	58.3	1082.0	13.0	169.1
USE	24.0	72.0	16.0	59.0	1082.0	13.0	170.0