

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1774	113(B-5,B-6)	LOGAN	60	4
STA. TO STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

ACRS		ACRS	
BRRP FUNDS	STP FUNDS	BRRP FUNDS	STP FUNDS
80% FED	80% FED	80% FED	80% FED
20% STATE	20% STATE	20% STATE	20% STATE
SN 054-0505	SN 054-2506	SN 054-0505	SN 054-2506
STA 1720+88 TO STA 1727+00		STA 1727+00 TO STA 1730+22	

CODE NO.	PAY ITEM	UNITS	TOTAL		CONSTRUCTION TYPE CODE	
			QUANTITY		X071-2A	X028-2A
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4	
63200310	GUARDRAIL REMOVAL	FOOT	234	188		46
63300575	REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	551	241		310
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	75	75		
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	898	418		480
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1			1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5			5
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	281	184		97
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	39	26		13
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,060	810		250
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,060	810		250
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	2,102	1,377		725
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	8		10
78300100	PAVEMENT MARKING REMOVAL	SQ FT	778	510		268
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	6		6
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1031	573		458
X0324118	GRANULAR CULVERT BACKFILL	CU YD	537			537
X3550700	BITUMINOUS BASE COURSE SUPERPAVE 10"	SQ YD	228			228
X3560140	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH	SQ YD	340	147		193

SUMMARY OF QUANTITIES

ACRS		ACRS	
BRRP FUNDS	STP FUNDS	BRRP FUNDS	STP FUNDS
80% FED	80% FED	80% FED	80% FED
20% STATE	20% STATE	20% STATE	20% STATE
SN 054-0505	SN 054-2506	SN 054-0505	SN 054-2506
STA 1720+88 TO STA 1727+00		STA 1727+00 TO STA 1730+22	

CODE NO.	PAY ITEM	UNITS	TOTAL		CONSTRUCTION TYPE CODE	
			QUANTITY		X071-2A	X028-2A
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	157		79	78
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	147		123	24
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	42		11	31
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 1	EACH	1		1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 2	EACH	1		1	
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	2			2
Z0002600	BAR SPLICERS	EACH	980		824	156
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		0.8	0.2
Δ Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		1	1
Δ Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2		1	1
* Z0054517	ROCK FILL - FOUNDATION	TON	100			100

Δ SFTY-3N
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAS 1774 (OLD IL 121)
SECTION 113(B-5, B-6)
LOGAN COUNTY

SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY: