CONTRACT NO. 76968

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/70	•	MADISON	11	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% MCHD SFTY-2A URBAN		
50102400	CONCRETE REMOVAL	CU YD	11.6	11.6		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	11.6	11.6		
50300300	PROTECTIVE COAT	SQ YD	36	36		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6760	6760		
50500505	STUD SHEAR CONNECTORS	EACH	147	147		
50501110	STRUCTURAL STEEL REMOVAL	POUND	6660	6660		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2770	2770		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	272	272		
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	272	272		
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	9	9		
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	9	9		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	57	57		
X0321781	MECHANICAL SPLICE	EACH	188	188		
Z0003600	BEAM STRAIGHTENING	L SUM	1	1		
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
Z0047300	PROTECTIVE SHIELD	SQ YD	45	45		
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	1		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES			

Δ SFTY-3N * SPECIALTY ITEMS

PLOT DATE = 8/31/2005
FILE NAME = c:\projects\ed11105\plan\pln11105a.dgn
PLOT SCALE = 49.9999 ' / IN.
REFERENCE = REF