

CODE NO	PAY ITEM	TOTAL		ELMHURST PARK DISTRICT		VILLAGE OF VILLA PARK		VILLAGE OF OAK BROOK		DUPAGE FOREST PRESERVE DISTRICT	
		UNIT	TOTAL QUANTITY	(1)		(2)		(3)		(4)	
				BIKE PATH	STRUCTURES	BIKE PATH	STRUCTURES	BIKE PATH	STRUCTURES	BIKE PATH	STRUCTURES
				YO47	X932-2A	YO47	N/A	YO47	X932-2A	YO47	N/A
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	992	575				315		102	
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	283	133				70		80	
20101200	TREE ROOT PRUNING	EACH	25					21		4	
M2020010	EARTH EXCAVATION	CU M	6,448	5923		3		512		10	
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	10,263	7801		259		1837		366	
M2040800	FURNISHED EXCAVATION	CU M	396			92		192		112	
M2070420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU M	852	529		41		230		52	
M2080150	TRENCH BACKFILL	CU M	89	21				62		6	
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	13,909	8,738		645		3702		824	
M2113150	TOPSOIL FURNISH AND PLACE, 150 MM	SQ M	27,232	20,205		676		5528		823	
M2130010	EXPLORATION TRENCH, SPECIAL	METER	20					20			
* M2500115	SEEDING, CLASS 1B	HA	1.1	0.4		0.1		0.5		0.1	
* M2500312	SEEDING, CLASS 4A	HA	0.9	0.7				0.1		0.1	
* M2500400	NITROGEN FERTILIZER NUTRIENT	KG	190	110		10		60		10	
* M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	190	110		10		60		10	
* M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	190	110		10		60		10	
* M2510105	MULCH, METHOD 1	HA	2.0	1.1		0.1		0.6		0.2	
* M2510630	EROSION CONTROL BLANKET	SQ M	2,200	1000		100		1000		100	
* M2520110	SODDING, SALT TOLERANT	SQ M	400	100		100		100		100	
M2520200	SUPPLEMENTAL WATERING	UNIT	8	4		1		2		1	
28000300	TEMPORARY DITCH CHECKS	EACH	25	16				5		4	
M2800400	PERIMETER EROSION BARRIER	METER	1,511	1073		208				230	
M2810103	STONE RIPRAP, CLASS A2	SQ M	12	12							
M2820200	FILTER FABRIC	SQ M	12	12							
M3511100	AGGREGATE BASE COURSE, TYPE B 100MM	SQ M	150	150							
M3511150	AGGREGATE BASE COURSE, TYPE B 150 MM	SQ M	11,734	7,369		537		3141		687	
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	10,515	6501		537		2790		687	
M4205200	PROTECTIVE COAT	SQ M	1,424	1,014		3		407			
M4240150	PORTLAND CEMENT CONCRETE SIDEWALK 150MM	SQ M	1,385	1006		6		373			
M4402000	PAVEMENT REMOVAL	SQ M	389	347				42			
M4402020	CURB REMOVAL	METER	16					16			
M4402045	COMBINATION CONCRETE CURB AND GUTTER	METER	44	36		4		4			
	REMOVAL AND REPLACEMENT										
M4812100	AGGREGATE SHOULDERS, TYPE B 100MM	SQ M	93	93							
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1.0						
M5010240	CONCRETE REMOVAL	CU M	11.4		10.0			1.4			
M5010465	SLOPE WALL REMOVAL	SQ M	265		85				180		
M5010522	PIPE CULVERT REMOVAL	METER	6					6			
M5020100	STRUCTURE EXCAVATION	CU M	398.9		205.9				193.0		
M5030350	CONCRETE STRUCTURES	CU M	346.9		185.7				161.2		

* SPECIALTY ITEM

REVISIONS		
NO.	NAME	DATE

URS 1701 GOLF ROAD, SUITE 1000 TEL (847) 228-0707
ROLLING MEADOWS, IL 60008 FAX (847) 228-1115

VILLAGE OF OAK BROOK
SALT CREEK GREENWAY TRAIL

SUMMARY OF QUANTITIES

DATE: 08/20/04 DRAWN BY: MIA&VP
DESIGNED BY: MIA CHECKED BY: DDL