SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
02-00034-00-BT	DUPAGE	108	4
STA.	TO STA.		
IDOT PROJECT NO. M-8003(216)			
SALT CREEK GREENWAY TRAIL			

CONTRACT NO. 83714

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	ELMHURST PARK DISTRICT (1)		VILLAGE OF VILLA PARK (2)		VILLAGE OF OAK BROOK (3)		DUPAGE FOREST PRESERVE DISTRICT (4)	
				BIKE PATH	STRUCTURES	BIKE PATH	STRUCTURES	BIKE PATH	STRUCTURES	BIKE PATH	STRUCTURES
				Y047	X932-2A	Y047	N/A	Y047	X932-2A	Y047	N/A
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	19,550		11,040				8,510		
M5100105	PIPE HANDRAIL	METER	291		179				112		
M5120160	FURNISHING STEEL PILES HP310X79	METER	272		238				34		
M5120166	FURNISHING STEEL PILES HP310X94	METER	51						51		
M5120315	DRIVING STEEL PILES	METER	323		238				85		
M5120460	TEST PILE STEEL HP310X79	EACH	4		3				1		
51204600	METAL SHOES	EACH	23		18				5		
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	24	12				8		4	
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	4	2				2			
M542H020	PIPE CULVERTS, CLASS A, TYPE 1 300MM	METER	114	36				66		12	
M542H030	PIPE CULVERTS, CLASS A, TYPE 1 450MM	METER	17	8				9			
M5500450	STORM SEWERS, CLASS A, TYPE 2 450MM	METER	51					51			
M5510025	STORM SEWER REMOVAL 300MM	METER	58					58			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	5					5			
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1					1			
M6020110	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1					1			
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1					1			
M6023515	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (600MM DEPTH)	EACH	1					1			
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3							
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1					1			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5	3				2			
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1					1			
60500050	REMOVING CATCH BASINS	EACH	1					1			
60500060	REMOVING INLETS	EACH	1					1			
M6060290	CONCRETE GUTTER, TYPE B	METER	74	18				56			
M6062200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.30	METER	33					33			
M6320030	GUARDRAIL REMOVAL	METER	19	19							
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	8	2		2		2		2	
67100100	MOBILIZATION	L SUM	1	0.5				0.5			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5				0.5			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.5				0.5			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5				0.5			
M7200100	SIGN PANEL - TYPE 1	SQ M	29.3	13.0		2.6		11.6		2.1	
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	1				1			
M7290100	METAL POST - TYPE A	METER	182.4	66.9		3.1		105.0		7.4	
* M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	134	104				30			
* M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	164	125				39			

* SPECIALTY ITEM

REVISIONS		
NO.	NAME	DATE

URS
1701 GOLF ROAD, SUITE 1000 TEL (847) 228-0707
ROLLING MEADOWS, IL 60008 FAX (847) 228-1115

VILLAGE OF OAK BROOK

SALT CREEK GREENWAY TRAIL

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

DATE: 7/20/05 DRAWN BY: MIA&VP

DESIGNED BY: MIA CHECKED BY: DDL