

TREE REMOVAL SCHEDULE

ELMHURST PARK DISTRICT

OAKBROOK

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
02-00034-00-BT	DUPAGE	108	8
STA.	TO STA.		
IDOT PROJECT NO. M-8003(216)			
SALT CREEK GREENWAY TRAIL			

CONTRACT NO. 83714

STATION	OFFSET		6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
	LT	RT		
18+034.5		3.0	9	
18+072.4		2.3	13	
18+084.8	2.5		9	
18+085.0		2.9	9	
18+100.5		3.0	6	
18+105.2	0.8		6	
18+110.0	3.3		7	
18+115.0	2.3		6	
18+116.5	1.2		6	
18+120.8		4.0	6	
18+130.6		1.0	6	
18+133.0	1.4		7	
18+140.5	1.0			19
18+141.2		3.0	7	
18+165.6	0.3		6	
18+167.1	0.4		10	
18+167.1		3.5	11	
18+171.4		1.7	9	
18+171.4		1.1	9	
18+174.5	0.6		9	
18+176.0		1.1	10	
18+177.7		3.1	13	
18+573.0	1.3		11	
18+574.7		3.1	8	
18+585.9		3.9	7	
18+593.0		2.7	7	
18+593.0		3.6	10	
18+612.8	3.8		10	
18+615.7		2.0	10	
18+618.5	1.6		6	
18+636.0	1.1		9	
18+637.5		2.2	7	
18+680.3		3.3	9	
18+682.6	2.8		7	
18+691.4		0.7	8	
18+694.0	1.8		6	
18+695.5	0.7		7	
18+695.5		0.7	7	
18+699.1	1.4		6	
18+727.1	0.6		6	
18+785.9		2.6	7	
18+786.3		1.8	8	
18+794.0	3.2		6	
21+394.0	2.4		9	
21+395.3	4.0		11	
21+400.0	0.9		13	

STATION	OFFSET		6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
	LT	RT		
21+403.0	2.5			16
21+412.0	2.0		8	
21+434.0	3.1		11	
21+439.6	1.6		8	
21+450.8		2.1		22
21+470.0	1.6		6	
21+502.5	2.2		11	
21+505.1	2.0			36
21+536.0		1.1	10	
21+545.3		2.1	14	
21+549.5		0.7	9	
22+280.0	4.6			25
22+280.6	4.2		6	
22+323.7		1.9	6	
22+325.3		2.5	6	
SUBTOTAL			465	118

STATION	OFFSET		6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
	LT	RT		
22+830.9	1.5		10	
22+876.7	0.0			15
22+887.0	0.1	2.9	13	
SUBTOTAL			23	15
23+245.8		1.0	15	
23+254.3	2.7		7	
23+258.8	2.4		8	
23+262.4	2.6		7	
23+281.7		2.9	7	
23+285.1		5.2	15	
23+288.2		4.1	7	
23+288.5		2.4	9	
23+290.1		3.2	12	
TOTAL			575	133

STATION	OFFSET		6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
	LT	RT		
23+356.3		1.0	6	
23+398.2	1.4		13	
23+403.6	1.3		11	
23+407.4	1.3		6	
23+410.2	1.4		7	
23+594.2		1.3	6	
23+934.9		2.5	14	
23+939.1		2.1	7	
23+960.4		3.4	9	
23+964.6		4.3	11	
24+203.4		4.1	6	
29+252.8	2.7			17
29+255.5		2.0	9	
29+258.5	0.8		8	
29+264.3		1.4	7	
29+267.5		2.6	10	
29+272.2	3.1		10	
29+283.3		2.6	10	
29+281.5	3.0		18	
29+281.5	3.2			16
29+282.2	3.0		10	
29+282.4	3.0		8	
29+285.0	3.3			20
29+285.0	3.9			18
29+285.1	3.2		12	
29+285.2	3.9		10	
29+293.1	4.4		9	
29+293.1	4.4		10	
29+293.6		3.0	12	
29+293.7		3.0	9	
29+296.5		2.5	13	
29+296.5		2.6	12	
29+298.0		1.4	8	
29+298.1		1.6	9	
29+300.6		2.1	14	
29+300.6		2.2	12	
TOTAL			315	70

STATION	OFFSET		6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
	LT	RT		

DUPAGE FOREST PRESERVE

STATION	OFFSET		6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
	LT	RT		
24+377.3		1.2	7	
24+379.4	1.3		6	
24+379.9		2.1	11	
24+383.0	1.8		6	
24+384.7		1.9	6	
24+388.6	0.9		13	
24+389.9		2.2	15	
24+396.2		2.1	9	
24+470.8	0.2		13	
24+472.9	1.3			28
24+480.6		0.2		31
24+491.0		1		21
24+497.4	1.3		15	
TOTAL			102	80

EARTHWORK SCHEDULE

LOCATION	SUITABLE EXCAVATION (EARTH EXCAVATION)	EARTH EX. ADJUSTED FOR SHRINKAGE (25%)	SUITABLE EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (FURNISHED EXCAVATION)	UNSUITABLE EXCAVATION (REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL)	UNSUITABLE EMBANKMENT	TOPSOIL FURNISH & PLACE 150MM	UNSUITABLE BALANCE WASTE (+) OR SHORTAGE (-)
	CU M	CU M	CU M	CU M	CU M	CU M	CU M	CU M
STA. 17+992 TO 18+831	895	671	916	-245	1595	0	623	+972
STA. 18+831 TO 19+010	3	2	286	-284	259	0	101	+158
STA. 21+263 TO 22+357	4848	3636	2186	1450	5571	0	2173	+3398
STA. 22+675 TO 23+003	3	2	468	-466	459	0	165	+294
STA. 23+200 TO 23+334.75	177	133	49	84	176	0	70	+106
STA. 23+334.75 TO 24+335	499	374	928	-554	1673	0	760	+913
STA. 24+335 TO 24+563.4	10	8	351	-343	366	0	124	+242
STA. 29+220 TO 29+311.9	13	10	48	-38	164	0	70	+94
TOTAL	6448	4836	5232	-396	10263	0	4086	+6177

REVISIONS		
NO.	NAME	DATE

URS 1701 GOLF ROAD, SUITE 1000 TEL. (847) 228-0707
 ROLLING MEADOWS, IL 60008 FAX. (847) 228-1115

VILLAGE OF OAK BROOK
SALT CREEK GREENWAY TRAIL
 TREE REMOVAL SCHEDULE
 EARTHWORK SCHEDULE

DATE: 7/20/05 DRAWN BY: MIA&VP
 DESIGNED BY: MIA CHECKED BY: DDL