

COUNTY HIGHWAY	FISCAL YEAR	TOTAL SHEETS	SHEET NO.
	2005	30	4
SEC 03-00001-06-BT		DUPAGE COUNTY	

CONTRACT NO.: 83805

TREE REMOVAL

STATION	OFFSET	6 - 15 UNITS	STATION	OFFSET	6 - 15 UNITS
5+27	11' RT	7"	14+55	15' RT	7"
5+36	2' LT	11"	15+13	13' RT	6"
8+12	15' RT	11"	15+89	1' RT	6"
8+28	5' LT	7"	16+15	13' RT	8"
8+33	7' LT	9"	17+99	13' RT	11"
8+52	9' LT	9"	19+08	15' RT	8"
9+03	14' RT	12"	19+68	15' RT	8"
9+16	5' LT	6"	20+17	3' LT	6"
9+56	15' RT	9"	20+41	7' RT	8"
9+79	3' RT	9"	23+19	8' LT	6"
10+17	5' RT	13"	23+26	17' RT	9"
10+49	21' RT	13"	23+54	7' LT	9"
11+38	15' RT	8"	26+54	15' RT	6"
12+11	7' RT	7"	27+45	14' RT	8"
13+07	5' RT	6"	27+67	1' RT	11"
13+32	15' RT	13"	28+35	5' LT	11"
13+88	11' RT	6"	31+06	18' RT	9"
14+43	2' RT	6"	39+95	7' LT	15"
			TOTAL		314 UNITS

EROSION CONTROL

STATION	OFFSET	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	STATION	OFFSET	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION
		28000300	28000500			28000300	28000500
5+01	23' RT	1		35+99	29' RT	1	
5+77	21' RT	1		37+55	30' RT	1	
6+53	20' RT	1		39+00	30' RT	1	
7+23	23' RT	1		2+31	16' RT		1
7+99	25' RT	1		4+62	22' RT		1
8+77	27' RT	1		4+39	19' RT		1
9+55	29' RT	1		8+51	7' LT		1
10+24	32' RT	1		10+04	6' LT		1
13+00	28' RT	1		10+75	34' RT		1
14+59	27' RT	1		23+19	8' LT		1
16+77	26' RT	1		24+18	27' RT		1
26+99	27' RT	1		25+71	27' RT		1
28+38	18' RT	1		36+72	10' LT		1
29+99	21' RT	1		40+17	6' LT		1
31+56	27' RT	1		41+08	22' RT		1
33+00	27' RT	1		41+45	6' LT		1
34+54	28' RT	1					
TOTALS		20	13				

FENCE

STATION	OFFSET	CHAIN LINK FENCE, 6'	CHAIN LINK FENCE REMOVAL
14+25	11' LT	20'	40'
33+07	15' LT	20'	40'
TOTALS		40'	80'

DRAINAGE

STATION	OFFSET	TRENCH BACKFILL	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	STORM SEWERS, CLASS A, TYPE 1 12" (FT)	STORM SEWERS, CLASS A, TYPE 1 15" (FT)	STORM SEWERS, CLASS A, TYPE 2 12" (FT)	STORM SEWERS, CLASS A, TYPE 2 36" (FT)	STORM SEWER REMOVAL 12" (FT)	STORM SEWER REMOVAL 15" (FT)	MANHOLES, TYPE A 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	CATCH BASINS TO BE ADJUSTED	CATCH BASINS TO BE RECONSTRUCTED	CATCH BASINS TO BE CLEANED	PLUG EXISTING STORM SEWER	REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTIONS
2+38	5' RT	18.20	54213657	550A0050	550A0070	25				60221100	60223800	60250200	60252800	60255410	Z0041700	XX003437
8+51	10' RT	5.04		26												
10+04	12.5' RT	5.63		29												
23+20	11' RT	10.91				32										
40+11	2' RT	10.92		15				15								
28+50	12' RT	2.14			7				6							
2+36	8.5' LT	15.08					10									
8+51	7' LT		1													
8+51	26' RT		1													
10+04	6' LT		1													
10+04	30.5' RT		1													
23+20	8' LT		1													
2+44	8' LT									1						
23+21	30.5' RT										1					
28+50	6' RT											1		1		
33+41	10' RT											1		1		
36+91	15' RT											1		1		
29+89	10' RT												1	1		
40+05	9' RT												1	1		
2+29	10' RT														2	
28+50	19' RT															1
TOTALS		68	5	70	7	57	10	15	6	1	1	3	2	5	2	1

	REM & DISP OF UNSUITABLE MATERIAL (PGES) (CU YD)	REM & DISP OF UNSUITABLE MATERIAL (TOPSOIL) (CU YD)	EARTH EXCAVATION (CU YD)	STORM SEWER EXCAVATION (CU YD)	TOTAL SUITABLE EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ FOR 15% SHRINKAGE) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
1+00 TO 10+00	0	353	432	38	470	400	220	+180
10+00 TO 20+00	0	388	617	6	623	530	48	+482
20+00 TO 30+00	0	435	734	13	747	635	91	+544
30+00 TO 41+57.13	0	503	885	11	896	762	188	+574
TOTALS	0	1,679	2,668	68	2,736	2,327	547	+1,780

6/9/2005 2:43:58 PM k:\119001\cadd\develop\901_schedules.dgn

NO.	DATE	BY	REVISION	NO.	DATE	BY	REVISION

SCALE	
DRAWN BY	JMC DATE
CHECKED BY	MRH DATE
APPROVED BY	DWB DATE



R/N GROUP, INC.
CONSULTING ENGINEERS

PROJECT: **Southern DuPage County Regional Trail**
101st Street Connector - Waterfall Glen Spur

TITLE: **SCHEDULES**

DATE: JUNE 9, 2005
PROJECT No: 11-1900-01
SHEET: