

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	7BR-P	Whiteside	21	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

GENERAL NOTES

Install a "TO ACTUATE SIGNAL" sign for the traffic signal detector loops. The detail of this sign is included in the plans. This work will be included in the cost of TRAFFIC CONTROL AND PROTECTION STANDARD 701316.

This structure will retain the same number 098-6003.

The contractor shall submit four copies of the required shop drawings for review and approval to the Bureau of Bridges and Structures, 2300 South Dirksen Parkway, Springfield, IL 62764. After approval of initial submittal, the contractor shall submit one set of shop drawings to Eric Harm, Engineer of Materials, 126 East Ash Street, Springfield, IL 62706, and eight (8) sets of shop drawings to be distributed to:

- District 2 District Engineer (1)
- Fabricator (1)
- Contractor (2)
- Resident Engineer (2)
- District 2 Bureau of Materials (2)

Work on this project will be in progress at the same time as work on the US Route 30/Dakin Road and US Route 30/Railroad bridge rehabilitation project 0.5 miles east of this project (Contract # 84883). Work on these projects shall be scheduled to keep interference between all the projects to a minimum. The contractors shall inform each other of progress of the projects and give fair warning to the other contractors when a problem might be encountered.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

- | | | | |
|--|--------------------------------|--|---------------------------|
| Mr. Dennis Jarding
Mediacom
3900 26th Avenue
Moline IL 61265 | CATV
309/7434750 | Mr. Mike Lenox
Commonwealth Edison Company
123 Energy Avenue
Rockford, IL 61109 | Electric
815/490-2869 |
| Mr. David Day
Frontier/Citizens Communications
684 N. Broad/PO Box 12
Lanark, IL 61046 | Communications
815/493-1101 | Mr. R.C. Meagher
US Sprint
5600 N River Road/Mail Stop: ILR0SA0504
Rosemont, IL 60018 | Telephone
847/318-3193 |
| Mr. Justin French
Lightcore
14567 N. Outer Forty Road, Suite 500
Chesterfield, MO 63017 | Communications
314/880-1637 | | |

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

- | | |
|---|----------------------|
| Mr. Dennis Schultz
IDOT-Dist 2
819 Depot Ave
Dixon, IL 61021 | GOVT
815/284-5469 |
|---|----------------------|

A Contingency item has been included for Joint Sealant - Steel. Contractor is to repair any damaged or weathered caulking that is no longer providing a seal. All new caulking that is installed shall be placed in a manner to provide positive drainage, i.e. not to entrap moisture behind mating steel surfaces. See Special Provisions.

A minimum of 4 air monitors will be required to monitor abrasive blasting operations at this site, see special provision for "Containment and Disposal of Lead Paint Cleaning Residues."

GENERAL NOTES
US 30 OVER MISSISSIPPI RIVER
FAP ROUTE 309 (US 30)
SECTION 7BR-P
WHITESIDE COUNTY
STRUCTURE NUMBER 098-6003