

# SUMMARY OF QUANTITIES

F.A.U. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-02-PV	MCLEAN	117	5
STA.	TO STA.			
	ILLINOIS			

CONTRACT NO. 87267

CODE NO.	ITEM	SAFETY CODE		2A	2A	1F		
		CONSTRUCTION CODE		J000	J000	Y031	Y060	Y060
		UNIT	TOTAL QUANTITY	HAMILTON ROAD 80% FEDERAL 20% CITY (1)	MORRIS AVENUE 80% FEDERAL 20% CITY (2)	TRAFFIC SIGNALS 80% FEDERAL 20% CITY	WATER MAIN** 100% CITY (1)	SANITARY SEWER** 100% CITY (2)
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	607	442	165			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	18196	6515	11681			
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	15242	14838	404			
44000006	BITUMINOUS SURFACE REMOVAL 1/2"	SQ YD	2103		2103			
44000100	PAVEMENT REMOVAL	SQ YD	7643	5469	2174			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2806	1910	896			
44000300	CURB REMOVAL	FOOT	78	78				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	457	215	242			
44000600	SIDEWALK REMOVAL	SQ FT	716		716			
44004000	PAVED DITCH REMOVAL	FOOT	20	20				
* 44004300	PAVEMENT BREAKING	SQ YD	1206		1206			
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	29	29				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	36					36
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	35				35	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	76					76
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1103		1103			
* 50105210	REMOVE EXISTING CULVERTS	FOOT	663	341	322			
* 54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2		2			
* 54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
* 54248515	CONCRETE COLLAR	EACH	10	4	6			
* 550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	207	61	146			
* 550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	84		84			
* 550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	173	173				
* 550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2050	1076	974			
* 550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	1430	1163	267			
* 550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1009	1009				
* 550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	345	345				
* 55100500	STORM SEWER REMOVAL 12"	FOOT	145	142	3			
* 55100700	STORM SEWER REMOVAL 15"	FOOT	12		12			
* 55101200	STORM SEWER REMOVAL 24"	FOOT	6	6				
+ * 56103300	DUCTILE IRON WATER MAIN 12"	FOOT	291				291	
+ * 56103400	DUCTILE IRON WATER MAIN 16"	FOOT	3188				3188	
+ * 56104400	WATER VALVES 1"	EACH	16				16	
+ * 56104500	WATER VALVES 1/2"	EACH	4				4	
+ * 56104900	WATER VALVES 6"	EACH	2				2	

\*SEE SPECIAL PROVISIONS  
 \*\*NON-PARTICIPATING WORK  
 + SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE : NONE  
 DATE : 3-05  
 DRAWN BY : J.L.B.  
 CHECKED BY : R.L.H.