

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-02-PV	MCLEAN	117	10
STA.		TO STA.		
ILLINOIS				

CONTRACT NO. 87267

CODE NO.	ITEM	SAFETY CODE		2A	2A	1F		
		CONSTRUCTION CODE		J000	J000	Y031	Y060	Y060
		UNIT	TOTAL QUANTITY	HAMILTON ROAD 80% FEDERAL 20% CITY (1)	MORRIS AVENUE 80% FEDERAL 20% CITY (2)	TRAFFIC SIGNALS 80% FEDERAL 20% CITY	WATER MAIN** 100% CITY (1)	SANITARY SEWER** 100% CITY (2)
* Z0022800	FENCE REMOVAL	FOOT	3488	1664	1752			72
+* Z0049801	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1		1			
* Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	2	2				
+* Z0059500	SANITARY SEWER, TYPE 2 6"	FOOT	105					105
+* Z0059600	SANITARY SEWER, TYPE 2 8"	FOOT	182					182
+* Z0060800	SANITARY SEWER, TYPE 3 6"	FOOT	400					400
+* Z0060900	SANITARY SEWER, TYPE 3 8"	FOOT	718					718
* Z0064225	SEALING ABANDONED WATER WELLS	EACH	1		1			
+* Z0068200	STEEL CASINGS 30"	FOOT	98				98	
Δ* Z0076600	TRAINEES	HOUR	1000	1000				
* XX006372	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 4"	FOOT	45		45			
* XX006373	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 8"	FOOT	42		42			
+* XX006374	DUCTILE IRON WATER MAIN 20" RESTRAINED JOINT TYPE	FOOT	74				74	
* XX006375	CHAIN LINK GATES, 5' X 24' DOUBLE (SPECIAL)	EACH	2	1	1			
* XX006376	CEMENT AGGREGATE MIXTURE (CAM II) 4"	SQ YD	19184	19184				
+* XX006377	SEPTIC TANK TO BE PUMPED	EACH	2					2
+* XX006378	SANITARY SEWER, TYPE 4 8"	FOOT	1481					1481
+* XX006379	CONDUIT AUGERED 3", HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	118			118		
+* XX006380	PHOTOCELL CONTROLLER	EACH	1			1		
47100100	Mobilization	L Sum	1	1				

*SEE SPECIAL PROVISIONS
 **NON-PARTICIPATING WORK Δ = 1080
 + SPECIALITY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 DATE : 3-05
 DRAWN BY : J.L.B.
 CHECKED BY : R.L.H.
 SCALE : NONE