

| | | | | |
|---------------------|----------------|------------------|--------------|-----------|
| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 642 | 99-00124-01-PV | COLES | 157 | 16 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

SUMMARY OF QUANTITIES

PAY LIMITS = 141+25 C.H. 18
102+50 TO APPROACHES ONLY
(BRIDGE & APPROACHES ONLY)
ICC ELIGIBLE

PAY LIMITS = 141+25 C.H. 18
102+50 TO APPROACHES ONLY
ICC ELIGIBLE

PAY LIMITS = 102+50 C.H. 18
141+25 TO 166+00 C.H. 18
ICC ELIGIBLE

| ITEM NUMBER | ITEM | UNIT | TOTAL QUANTITY | X571-2A | J000-2A | X571-2A |
|-------------|---|---------|----------------|---------|---------|---------|
| 61101020 | STORM SEWER PROTECTED, CLASS A, 18" | FOOT | 120 | | | 120 |
| 61101026 | STORM SEWER PROTECTED, CLASS A, 24" | FOOT | 120 | | | 120 |
| 61133100 | FIELD TILE JUNCTION VAULTS, 2' DIA. | EACH | 8 | | | 8 |
| 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 3413 | 3413 | | |
| 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 4 | 4 | | |
| 63100169 | TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) | EACH | 4 | 4 | | |
| 63500105 | DELINEATORS | EACH | 32 | 28 | | 4 |
| 66101120 | BITUMINOUS SHOULDER CURB | FOOT | 3459 | 3459 | | |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | 46 | 15 | 13 | 18 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 16 | 5 | 2 | 9 |
| 67000600 | ENGINEER'S FIELD LABORATORY | CAL MO | 16 | 5 | 2 | 9 |
| 67100100 | MOBILIZATION | L SUM | 1 | | | 1 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | | 1 | |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | | 1 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 500 | | 500 | |
| 70300220 | TEMPORARY PAVEMENT MARKING-LINE 4" | FOOT | 4925 | 425 | 4500 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1808 | | 1808 | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 165 | 165 | | |
| 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 149 | 45 | 104 | |
| 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 67 | 26 | 41 | |
| 72800100 | TELESCOPING STEEL SIGN SUPPORT | FOOT | 550 | 129 | 421 | |
| *78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 156 | | 156 | |
| *78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 12791 | | 12791 | |
| *78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 263 | | 263 | |
| *78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 11755 | 4163 | 3496 | 4096 |
| *78005100 | EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 437 | 312 | 125 | |
| *78005110 | EPOXY PAVEMENT MARKING - LINE 4" | FOOT | 24030 | 15764 | 654 | 7612 |
| *78005150 | EPOXY PAVEMENT MARKING - LINE 12" | FOOT | 1011 | 527 | 354 | 130 |
| *78005180 | EPOXY PAVEMENT MARKING - LINE 24" | FOOT | 63 | | 63 | |
| *78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 156 | | 156 | |
| *78200100 | MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR | EACH | 8 | 8 | | |
| *78200300 | PRISMATIC CURB REFLECTOR | EACH | 6 | | 6 | |
| *78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 15 | 15 | | |
| *78201000 | TERMINAL MARKER -DIRECT APPLIED | EACH | 4 | 4 | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 2515 | | 2515 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 156 | | 156 | |
| X0321100 | GEOTEXTILE RETAINING WALL | SQ FT | 804 | | 804 | |
| X3550600 | BITUMINOUS BASE COURSE SUPERPAVE 9" | SQ YD | 2219 | | 2219 | |
| X4066426 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70 | TON | 771 | | 771 | |
| X6020073 | INLETS, TYPE A, TYPE B GRATE, TEMPORARY | EACH | 1 | | | 1 |
| X7015005 | CHANGEABLE MESSAGE SIGN | CAL DAY | 14 | | 14 | |
| XX002909 | CLASS SI CONCRETE | CU YD | 2.3 | | 2.3 | |
| X0322024 | TRENCH DRAIN | EACH | 1 | | 1 | |
| XX006414 | PORTLAND CEMENT CONCRETE BASE COURSE, 8" (SPECIAL) | SQ YD | 86 | | 86 | |
| XZ193300 | SURVEY MARKER, TYPE 1 (SPECIAL) | EACH | 1 | | 1 | |
| Z0000990 | AGGREGATE FOR TEMPORARY ACCESS | TON | 150 | 150 | | |
| Z0002600 | BAR SPLICERS | EACH | 80 | 80 | | |
| Z0007601 | BUILDING REMOVAL NO. 1 | L SUM | 1 | | | 1 |
| Z0007602 | BUILDING REMOVAL NO. 2 | L SUM | 1 | | | 1 |
| Z0007603 | BUILDING REMOVAL NO. 3 | L SUM | 1 | | | 1 |
| Z0007604 | BUILDING REMOVAL NO. 4 | L SUM | 1 | | | 1 |
| Z0030900 | INSPECTION WELLS | EACH | 16 | 16 | | |
| Z0037300 | PAVEMENT GROOVING (Approach Slabs) | SQ. YD. | 279 | 279 | | |
| Z0038700 | PERMANENT BENCH MARKS (At Bridges) | EACH | 2 | 2 | | |
| Z0047300 | PROTECTIVE SHIELD | SQ YD | 473 | 255 | 218 | |
| Z0048665 | RR LIABILITY & PROTECTION INSURANCE | L SUM | 1 | 1 | | |
| Z0049801 | REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS BUILDING NO. 1 | L SUM | 1 | | | 1 |
| Z0049904 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS BUILDING NO. 4 | L SUM | 1 | | | 1 |
| XX004056 | MECHANICALLY STABILIZED EARTH RETAINING WALL | SQ FT | 17341 | | 17341 | |
| XX006411 | US 45 DETOUR | L SUM | 1 | | 1 | |
| XX006412 | COARSE AGGREGATE EMBANKMENT (SPECIAL) | CU YD | 3266 | 3266 | | |
| XX006413 | GUARDRAIL AGGREGATE EROSION CONTROL | CU YD | 243 | 243 | | |

*SPECIALTY ITEMS

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---|
| NAME | DATE | |
| | | SUMMARY OF QUANTITIES SCALE: VERT. DRAWN BY RLH HORIZ. CHECKED BY MED DATE 09/02/2005 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

TUG PROJ #13107022-5
SHEET W.dgn
09/02/2005