

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-01-PV	COLES	157	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVING SCHEDULE

STA. TO STA.	PCC PAVEMENT 8" (JOINTED) SQ. YD.	BRIDGE APPROACH PAVEMENT SQ. YD.	BRIDGE APPROACH PAVEMENT (SPECIAL) SQ. YD.	PROTECTIVE COAT SQ. YD.	BIT. CONCRETE SURFACE COURSE SUPERPAVE, MIX D TON	BITUMINOUS SHOULDERS SUPERPAVE, 8" SQ. YD.	BITUMINOUS SHOULDERS TON	AGGREGATE SHOULDERS, TYPE B, 6" SQ. YD.	STABILIZED SUBBASE, 4" SQ. YD.
COUNTY HIGHWAY 18									
100+00.00 TO 111+00.00	4561.0			4575.8		918.9		488.3	4889.2
111+00.00 TO 120+29.00	2784.7	138		2989.9		1598.4			3085.4
123+45.50 TO 126+00.00	598.6		141	755.5		205.0			674.8
126+00.00 TO 141+00.00	6047.0			6091.4		1343.4		232.9	6547.0
141+00.00 TO 156+00.00	4129.0			4129.0		831.7		841.9	4629.0
156+00.00 TO 166+00.00	3016.0			3016.0		612.2		573.0	3316.2
JUGHANDLE									
100+30.00 TO 106+00.00	1948.0			1948.0		334.2		327.0	2139.8
106+00.00 TO 116+58.21	3865.0			3865.0		634.4		626.4	4240.5
US ROUTE 45									
97+50.00 TO 102+50.00					35.8	90.8		90.7	
102+50.00 TO 117+50.00					517.1	936.8		942.1	
117+50.00 TO 127+25.00					218.4	441.6	47	441.7	
LOGAN STREET	709.0			709.0					772.7
PROJECT TOTAL	27658.3	138	141	28079.6	771.3	7947.4	47	4564.0	30294.6

STA. TO STA.	LIME MODIFIED SOILS, 12" SQ. YD.	LIME TON	WATER UNIT	BITUMINOUS CONCRETE BASE COURSE SUPERPAVE, 9" SQ. YD.	SUBBASE GRANULAR MATERIAL TYPE B, 4" SQ. YD.	STRIP REFLECTIVE CRACK CONTROL LIN. FT.	PCC SHOULDERS, 8" SQ. YD.	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON
COUNTY HIGHWAY 18									
100+00.00 TO 111+00.00	4889.2	110.0	24.4				14.8	45.9	
111+00.00 TO 120+29.00	3085.4	69.4	15.4				67.2	79.9	
123+45.50 TO 126+00.00	674.8	15.2	3.4				15.9	10.3	
126+00.00 TO 141+00.00	6547.0	147.3	32.7				44.4	67.2	
141+00.00 TO 156+00.00	4629.0	104.2	23.1					41.6	
156+00.00 TO 166+00.00	3316.2	74.6	16.6					30.6	
JUGHANDLE									
100+30.00 TO 106+00.00	2139.8	48.1	10.7					16.7	
106+00.00 TO 116+58.21	4240.5	95.4	21.2					31.7	
US ROUTE 45									
97+50.00 TO 102+50.00				63.0	93.2	272		44.0	0.7
102+50.00 TO 117+50.00				2155.9	2408.8	2458		554.6	8.0
117+50.00 TO 127+25.00								337.7	5.2
LOGAN STREET	772.7	17.4	3.9						
PROJECT TOTAL	30294.6	681.6	151.5	2218.9	2502.0	2730	142.3	1260.2	13.9

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVING SCHEDULE

SCALE: VERT.
HORIZ.
DATE 04/08/2005

DRAWN BY SJF
CHECKED BY MED

TUG PROJ #1917022-5
-PAVING SCHEDULE-W.dgn
04/08/2005