SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN 80% FED. 20% STATE)	CONSTRUCTION TYPE CODE 0044					
20200100	EARTH EXCAVATION	CU YD	89.5	89.5					
*21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	963	963					
21400100	GRADING AND SHAPING DITCHES	FOOT	250	250					
*25000210	SEEDING, CLASS 2A	ACRE	0.07	0.07					
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	15					
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15	15					
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	15					
*25100630	EROSION CONTROL BLANKET	SQ YD	963	963					
*25200100	SODDING	SQ YD	620	620					
28000400	PERIMETER EROSION BARRIER	FOOT	758.5	758.5					
28000500	INLET AND PIPE PROTECTION	EACH	2	2					
55100900	STORM SEWER REMOVAL 18"	FOOT	198	198					
55101200	STORM SEWER REMOVAL 24"	FOOT	125	125					
55101400	STORM SEWER REMOVAL 30"	FOOT	130	130					
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	3	3					
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60500040	REMOVING MANHOLES	EACH	2	2					
60500050	REMOVING CATCH BASINS	EACH	1	1					
67100100	MOBILIZATION	L SUM	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
70100450	TRAFFIC CONTROL & PROTECTION, STD. 701201	L SUM	1	1					
X5521500	STORM SEWERS JACKED IN PLACE, 42" SPECIAL	FOOT	291	291					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	104	104					
△1 Z0056626	STORM SEWERS (WATERMAIN REQUIREMENTS), 48"	FOOT	453	453					
Z0068412	STEEL CASINGS, 54"	FOOT	291	291					
△1 550A0410	STORM SEWER CLASS A, TYPE 2, 24"	FOOT	10	10					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					

*SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

△1 Rev. 11-7-11

FILE NAME = c:\pw_work\pwidot\leysd\dms89282\D107406-sht-drain.dgn	USER NAME = leysd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 8/29/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-55 EAST OF IL-53 DRAINAGE IMPROVEMENT
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 3 OF SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	29T-1	WILL	19	3

CONTRACT NO. 60A56

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Rev.