SUMMARY OF QUANTITIES

	CODED PAY ITEM NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED./20% STATE CONSTRUCTION TYPE CODE ROADWAY 0003	MINOR STRUCTURES 0040	LANDSCAPING 0031
*	20101100	TREE TRUNK PROTECTION	EACH	13	13		
*	20101200	TREE ROOT PRUNING	EACH	50			50
*	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	20			20
*	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	20			20
	20200100	EARTH EXCAVATION	CU YD	15720	15720		
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	30897	30897		
	20400800	FURNISHED EXCAVATION	CU YD	20180	20180		
	20800150	TRENCH BACKFILL	CU YD	679	679		
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	10776	10776		
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	31466			31466
*	21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	16444			16444
*	25000210	SEEDING, CLASS 2A	ACRE	3.25			3.25
*	25000310	SEEDING, CLASS 4	ACRE	2.75			2.75
*	25000314	SEEDING, CLASS 4B	ACRE	0.75			0.75
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	585			585
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	585			585
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	585			585
*	25100115	MULCH, METHOD 2	ACRE	7.00			7.00
*	25100630	EROSION CONTROL BLANKET	SQ YD	31466	31466		
*	25200110	SODDING, SALT TOLERANT	SQ YD	490			490
*	25200200	SUPPLEMENTAL WATERING	UNIT	10			10
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	650	650		
*	28000305	TEMPORARY DITCH CHECKS	FOOT	868	868		
*	28000400	PERIMETER EROSION BARRIER	FOOT	9757	9757		
	28000510	INLET FILTERS	EACH	62	62		
	28100107	STONE RIPRAP, CLASS A4	SQ YD	124	119	5	

* INDICATES SPECIALTY ITEMS

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED./20% STATE CONSTRUCTION TYPE CODE ROADWAY 0003	MINOR STRUCTURES 0040	LANDSCAPING 0031
28200200	FILTER FABRIC	SQ YD	119	119		
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	651	651		
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	40411	40411		
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	269	269		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	115	115		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	31	31		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	43	43		
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	36647	36647		
42001300	PROTECTIVE COAT	SQ YD	43673	43673		
44000100	PAVEMENT REMOVAL	SQ YD	23869	23869		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	339	339		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	515	515		
44003100	MEDIAN REMOVAL	SQ FT	8995	8995		
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	1074	1074		
50104400	CONCRETE HEADWALL REMOVAL	EACH	8	8		
50105220	PIPE CULVERT REMOVAL	FOOT	556	556		
50300225	CONCRETE STRUCTURES	CU YD	326.8		326.8	
50500505	STUD SHEAR CONNECTORS	EACH	3182		3182	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	30620		30620	
51500100	NAME PLATES	EACH	6		6	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4		4	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	7		7	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1	
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	6		6	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1		1	
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	1		1	
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	93		93	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	96		96	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	48		48	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	3210		3210	

* INDICATES SPECIALTY ITEMS

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME — NOTE BOOK NO. — BY — DATE

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME — NOTE BOOK NO. — BY — DATE