

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

CONSTRUCTION TYPE CODE

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY 0003	MINOR STRUCTURES 0040	LANDSCAPING 0031
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	802		802	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	627		627	
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	336		336	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	71		71	
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	86		86	
550A0380	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	8		8	
550A0450	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	85		85	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	542		542	
60107600	PIPE UNDERDRAINS 4"	FOOT	840		840	
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	29		29	
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3		3	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	21		21	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7		7	
60223600	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1	
60224400	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1	
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	34		34	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	12		12	
60500040	REMOVING MANHOLES	EACH	2		2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10864	10864		
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	569	569		
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	187	187		
60618210	HOT-MIX ASPHALT MEDIAN SURFACE, 4 INCH	SQ FT	3093	3093		
60618740	CONCRETE MEDIAN, TYPE M-2.12	SQ FT	820	820		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	3025.0	3025.0		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
63200310	GUARDRAIL REMOVAL	FOOT	302	302		

* INDICATES SPECIALTY ITEMS

80% FED. / 20% STATE

CONSTRUCTION TYPE CODE

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY 0003	MINOR STRUCTURES 0040	LANDSCAPING 0031
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18		
67100100	MOBILIZATION	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	171	171		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16075	16075		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3500.0	3500.0		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1612.5	1612.5		
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	255	255		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	24606	24606		
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	995	995		
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	826	826		
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	60	60		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	652	652		
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	372	372		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1006	1006		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	285	285		
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	241	241		
* 81400100	HANDHOLE	EACH	1	1		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	241	241		
* 86200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	1	1		
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	432	432		
* 87900200	DRILL EXISTING HANDHOLE	EACH	1	1		
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	3	3		
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3	3		
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1		
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1	1		

* INDICATES SPECIALTY ITEMS

DATE: _____
 BY: _____
 SURVEYED: _____
 PLOTTED: _____
 ALIGNED: _____
 CHECKED: _____
 CADD FILE NAME: _____
 PLAN NO.: _____

DATE: _____
 BY: _____
 SURVEYED: _____
 PLOTTED: _____
 ALIGNED: _____
 CHECKED: _____
 CADD FILE NAME: _____
 PLAN NO.: _____

FILE NAME = ...\\0160135-sht-5002.dgn



DESIGNED RJD
 DRAWN MHL
 CHECKED RJD
 DATE JUNE 30, 2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**IL RTE 62 (ALGONQUIN RD.) FROM EASTING'S WAY TO PENNY RD.
 SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 339	SECTION 116 Y-1-R-1	COUNTY COOK	TOTAL SHEETS 122	SHEET NO. 5
CONTRACT NO. 60135			ILLINOIS FED. AID PROJECT	

Rev.