

SCHEDULE OF QUANTITIES

LOCATION STA TO STA	EARTHWORK									
	UNDERCUT AND PGE REPLACEMENT (CU YD)	UNSUITABLE EXCAVATION (TOPSOIL) (CU YD)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EARTH EXCAVATION (CU YD)	UTILITY EXCAVATION (CU YD)	EXCESS STRUCTURE EXCAVATION (CU YD)	TOTAL SUITABLE EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
IL ROUTE 31	167	982	1,149	4,962	11	-	4,973	4,228	998	3,230
AMES ROAD	-	40	40	148	-	-	148	126	20	106
EDGEWOOD ROAD	42	61	103	195	-	-	195	166	16	150
TOTAL	209	1,083	1,292	5,305	11	-	5,316	4,520	1,034	3,486

COMPUTER - 2011 BY BAXTER & WOODMAN, INC. \\dot\id\year\VDI72434.dft
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 084-20121 - EXPIRES 4/30/2011
 4/16/10 11:52:37 AM 11/25/2011



DESIGNED - DJS	REVISED - 1-28-11 PER IDOT REVIEW
DRAWN - CJC	REVISED - 3-14-11 PER IDOT REVIEW
CHECKED - LDH	REVISED -
DATE - 09/10/10	FILE - 100153.W05-schedule.sht

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 31 - AMES ROAD TO EDGEWOOD ROAD
SCHEDULE OF QUANTITIES**

SCALE: STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	2010-049-N	MCHENRY	50	8
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 60L25	