

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 90% FED. 10% STATE LS3E	ROADWAY 90% FED. 10% STATE LS3E	MULTI-USE PATH 100% COUNTY 07ND	TRAFFIC SIGNAL 90% FED. 5% STATE 5% COUNTY LS3E	EMERGENCY VEHICLE PREEMPTION 100% CITY 07PO	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 90% FED. 10% STATE	ROADWAY 90% FED. 10% STATE	MULTI-USE PATH 100% COUNTY	TRAFFIC SIGNAL 90% FED. 5% STATE 5% COUNTY	EMERGENCY VEHICLE PREEMPTION 100% CITY
				0004	0005	0028	0021	0021					0004	0005	0028	0021	0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	122	122					42001300	PROTECTIVE COAT	SO YD	104	100		4		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30					42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	60	60				
20101200	TREE ROOT PRUNING	EACH	5	5					42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	200		200			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5					42400800	DETECTABLE WARNINGS	SO FT	85		85			
20200100	EARTH EXCAVATION	CU YD	3667	3667					44000100	PAVEMENT REMOVAL	SO YD	150	150				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3315	3315					44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	17500	7900	9600			
20800150	TRENCH BACKFILL	CU YD	10	10					44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	675	675				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	7825	7825					44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	150	150				
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	25,890	25,890					44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SO YD	1030	475	555			
21400100	GRADING AND SHAPING DITCHES	FOOT	4460	4460					44003100	MEDIAN REMOVAL	SO FT	540	540				
* 25000210	SEEDING, CLASS 2A	ACRE	5.3	5.3					44004250	PAVED SHOULDER REMOVAL	SO YD	3105	3105				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	475	475					44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	220	100	120			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	475	475					44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	310	140	170			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	475	475					44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	365	175	190			
* 25100630	EROSION CONTROL BLANKET	SO YD	25,890	25,890					48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	4150	4150				
* 25200200	SUPPLEMENTAL WATERING	UNIT	1	1					50105220	PIPE CULVERT REMOVAL	FOOT	160	160				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	530	530					54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6	6				
28000305	TEMPORARY DITCH CHECKS	FOOT	22	22					542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	161	161				
28000400	PERIMETER EROSION BARRIER	FOOT	4925	4925					60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	11	11				
28000500	INLET AND PIPE PROTECTION	EACH	12	12					60107600	PIPE UNDERDRAINS 4"	FOOT	550	550				
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	665	665					60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	180	180				
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	950	75		875			60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	120	120				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	175	175					* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1125	1125				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	480	480					* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
35501330	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SO YD	3150	3150					* 66900530	SOIL DISPOSAL ANALYSIS	EACH	8	8				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	13	8	1			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
40600300	AGGREGATE (PRIME COAT)	TON	91	49	40	2			67100100	MOBILIZATION	L SUM	1	1				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	27	12	15				70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1			
40600895	CONSTRUCTING TEST STRIP	EACH	3	2		1			70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1		1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	65	65					70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	130	60	70				70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1		1			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	185	85		100			70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1745	935	810												

* SPECIALTY ITEMS