

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE 0014
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	66	66	0
20101100	TREE TRUNK PROTECTION	EACH	11	11	0
20200100	EARTH EXCAVATION	CU YD	10	10	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	58	58	0
20400800	FURNISHED EXCAVATION	CU YD	89	89	0
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	657	657	0
25000210	SEEDING, CLASS 2A	ACRE	0.14	0.14	0.00
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	12	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	12	12	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	12	0
25100630	EROSION CONTROL BLANKET	SQ YD	657	657	0
28000400	PERIMETER EROSION BARRIER	FOOT	594	594	0
28000510	INLET FILTERS	EACH	2	2	0
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	73	73	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	41	41	0
40600300	AGGREGATE (PRIME COAT)	TON	1	1	0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	9	9	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	17	17	0
42001300	PROTECTIVE COAT	SQ YD	55	55	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	134	134	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	145	145	0
44000600	SIDEWALK REMOVAL	SQ FT	596	596	0
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	5	5	0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	0	1
50102400	CONCRETE REMOVAL	CU YD	3.6	0.0	3.6
50104000	BRIDGE RAIL REMOVAL	FOOT	196	0	196
50300255	CONCRETE SUPERSTRUCTURE	CU YD	42.3	0.0	42.3
50300260	BRIDGE DECK GROOVING	SQ YD	139	0	139
50300300	PROTECTIVE COAT	SQ YD	320	0	320
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1,877	0	1,877
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8,580	0	8,580
50900105	ALUMINUM RAILING, TYPE L	FOOT	180	0	180
51500100	NAME PLATES	EACH	1	0	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	40.5	0.0	40.5

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE 0014
59000200	EPOXY CRACK INJECTION	FOOT	60	0	60
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	138	138	0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	150	150	0
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3	0
63200310	GUARDRAIL REMOVAL	FOOT	374	374	0
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	0
67100100	MOBILIZATION	L SUM	1.0	1.0	0.0
* 78000200	<del>THERMOPLASTIC PAVEMENT MARKING LINE 4"</del>	<del>FOOT</del>	<del>307</del>	<del>307</del>	<del>0</del>
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5/2	5/2	0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	0
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	0	4
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	8	8	0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7	0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	0
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	0
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	180	180	0
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	214	0	214
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	1.0	0.0
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	3	3	0
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	28	0	28
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	5	0	5
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0	1.0	0.0
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	0
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1	0

\* SPECIALTY ITEMS

FILE NAME: g:\projects\2102195\_01\0\ood\civil\shs\011664\_03ant-303.dgn



USER NAME = ZPIEND	DESIGNED - DJB	REVISED -
PLOT SCALE = 50,0000' / IN.	DRAWN - ENTRAN	REVISED -
PLOT DATE = 8/31/2011	CHECKED - TMH	REVISED -
	DATE - 08/02/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SHERMER ROAD OVER MIDDLE FORK NORTH BRANCH CHICAGO RIVER  
SUMMARY OF QUANTITIES**

SCALE: 50,000' / IN. SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 2760	SECTION 100-B-1	COUNTY COOK	TOTAL SHEETS 28	SHEET NO. 3
CONTRACT NO. 60M80			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

Rev