

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				URBAN - 80% FEDERAL, 20% STATE		100% VILLAGE
				ROADWAY 0004	STRUCTURAL 0014	LIGHTING 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	6		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	250	60		190
25000210	SEEDING, CLASS 2A	ACRE	0.1			0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	1		3
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	1		3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	1		3
25200200	SUPPLEMENTAL WATERING	UNIT	8	2		6
44000100	PAVEMENT REMOVAL	SQ YD	74	74		
50102400	CONCRETE REMOVAL	CU YD	26.1		26.1	
50157300	PROTECTIVE SHIELD	SQ YD	60		60	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	26.1		26.1	
50300300	PROTECTIVE COAT	SQ YD	91		91	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6,040		6,040	
50800515	BAR SPLICERS	EACH	70		70	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	241		241	
58700300	CONCRETE SEALER	SQ FT	195		195	
59000200	EPOXY CRACK INJECTION	FOOT	6		6	
60624600	CORRUGATED MEDIAN	SQ FT	663	663		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3,133	3,133		

* DENOTES SPECIALTY ITEM



USER NAME = wloncaster
 PLOT SCALE = 1:80000' / IN.
 PLOT DATE = 9/9/2011

DESIGNED - JMV
 DRAWN - JMK
 CHECKED - JMV
 DATE - 9/2/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

ILL. 50 OVER THE CAL SAG CHANNEL
 STRUCTURE NO. 016-0421
 SUMMARY OF QUANTITIES

SCALE: 1" = 20' SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	3068 A-B-R-1	COOK	57	3
CONTRACT NO. 60N88				
ILLINOIS FED. AID PROJECT				