

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				URBAN - 80% FEDERAL, 20% STATE	100% VILLAGE	
				ROADWAY 0004	STRUCTURAL 0014	LIGHTING 0021
70400100	TEMPORARY CONCRETE BARRIER	FOOT	625	625		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	600	600		
• 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	36	36		
• 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	6,794	6,794		
• 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	165	165		
• 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FT	124	124		
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	103	103		
• 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	38	38		
• 78200530	BARRIER WALL MARKERS, TYPE C	EACH	100	100		
78300100	PAVEMENT MARKING REMOVAL	SO FT	2,510	2,510		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	141	141		
• 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1		
• 81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	85	85		
• 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	670	670		
• 81100510	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	630			630
• 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	10			10
• 81300320	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8" X 8" X 6"	EACH	9	6		3
• 81300810	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 8"	EACH	3	1		2
• 81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	280			280
• 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2,500	2,500		
• 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1,920			1,920
• 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	365	365		
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4			4
• 82200605	WATERWAY OBSTRUCTION WARNING LUMINAIRE, LED	EACH	6	6		
• 83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	1			1

• DENOTES SPECIALTY ITEM



USER NAME = wloncaster	DESIGNED - JMV	REVISED -
PLDT SCALE = 1:8000' / IN.	DRAWN - JMK	REVISED -
PLDT DATE = 9/9/2011	CHECKED - JMV	REVISED -
	DATE - 9/2/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILL. 50 OVER THE CAL SAG CHANNEL
STRUCTURE NO. 016-0421
SUMMARY OF QUANTITIES

SCALE: 1" = 20' SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	3068 A-B-R-1	COOK	57	4
CONTRACT NO. 60N88			ILLINOIS FED. AID PROJECT	

Rev.