

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAI 290	2011-061 BR	COOK & DUPAGE	29	4

CONTRACT NO. 60P79

SUMMARY OF QUANTITIES

CODE NO	DESCRIPTION	UNITS	URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE: SFTY - 0014		
				DuPAGE COUNTY	DuPAGE COUNTY	COOK COUNTY
				LOC. NO. 1 SN:022-0015	LOC. NO. 2 SN:022-0109	LOC NO. 3 SN 016-0986
50300225	CONCRETE STRUCTURES	CU YD	8.3		8.3	
50800205	REINFORCEMENT BAR, EPOXY COATED	POUND	1550		1550	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1.5	2	0.5
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1			1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FT	350		350	
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FT	100		100	
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	4		4	
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	4		4	
* 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	4		4	

* Special

ILLINOIS DEPARTMENT OF
TRANSPORTATION
SUMMARY OF QUANTITIES